Commonwealth of Massachusetts Executive Office of Environmental Affairs ■ MEPA Office

Environmental Notification Form

For Office Her O. I.	•
For Office Use Only	
Executive Office of Environmental Affairs	
- Joseph January Commentation	

EOEA No.: /32 //
MEPA Analyst: B: // GAGE
Phone: 617-626-

The information requested on this form must be completed to begin MEPA Review in accordance with the provisions of the Massachusetts Environmental Policy Act, 301 CMR 11.00.

Decided Name of Code (D)						
Project Name: Limited Removal of V Approximately 0.2 acres of Wetland	Wetland S	ioil/Sediment and	Restoration of			
Street: 50 Fordham Road		·		·		
Municipality: Wilmington- with wetland in		Watershed: Ipswich				
North Reading		, , , , , , , , , , , , , , , , , , ,				
Universal Tranverse Mercator Coord	dinates:	Latitude: 42 33 38				
		Longitude: 71 08 10				
Estimated commencement date: 3/1/04		Estimated completion date: 5/1/04				
Approximate cost: To be determined		Status of project	%complete			
Proponent: TRC Environmental Cor	poration					
Street: 31 Milk Street, Suite 1104		0	I —			
Municipality: Boston		State: MA	Zip Code: 02109			
Name of Contact Person From Who Paola Macchiaroli	m Copies	of this ENF May	Be Obtained:			
Firm/Agency: TRC		Stroots Od Mills C	Name On the 4404			
Municipality: Boston		State: MA	Street, Suite 1104			
Phone: (617) 350-9997	Fay: (61		Zip Code: 02109			
(011) 000 000.	1 ax. (01	7) 000-0440	E-mail: paola@trcsolution	s.com		
Does this project meet or exceed a mar	ndatory Elf	R threshold (see 301)	CMR 11 03\?			
	L]Y	es	⊠No			
Has this project been filed with MEPA b						
Has any project on this site been filed w	∰ AEDA	es (EOEA No) 🖾 No			
That any project of this site been filed w		es (EOEA No) 🛛 No			
Is this an Expanded ENF (see 301 CMR 11.0		· —				
a Single EIR? (see 301 CMR 11.06(8))	o(/)) reque	TYes	⊠No			
a Special Review Procedure? (see 301Cl	MR 11.09)	□Yes	⊠No			
a Waiver of mandatory EIR? (see 301 CM	/R 11.11)	☐Yes	⊠No			
a Phase I Waiver? (see 301 CMR 11.11)		∐Yes	⊠No			
Identify any financial assistance or land transfer from an agency of the Commonwealth, including						
the agency name and the amount of funding or land area (in acres): None						
Are you requesting coordinated review	with any ot	her federal, state, i	regional, or local agen	cy?		
☐Yes(Specify)	NO			
List Local or Federal Permits and Approvals						
Order of Conditions, North Reading Conservation Commission (DEP File # 245 1029)						
401 Water Quality Certification, Major P	roject		•			
Army Corps Programmatic General Permit – Category II						

☐ Land ☐ Water ☐ Energy ☐ ACEC	☐ Wastewater ☐ Transportat			zardous Waste . Archaeological
Summary of Project Size	Existing	Change	Total	State Permits &
& Environmental Impacts				Approvals
Total site acreage	LAND 3.91 (N. Reading)			Order of Conditions Superseding Order of Conditions
New acres of land altered		0		☐ Chapter 91 License ☑ 401 Water Quality
Acres of impervious area	0	0	0	Certification
Square feet of new bordering vegetated wetlands alteration		9,637.8 s.f.		MHD or MDC Access Permit
Square feet of new other wetland alteration		0		
Acres of new non-water dependent use of tidelands or waterways		0		☐ DEP or MWRA Sewer Connection/ Extension Permit
STR	JCTURES			Other Permits (including Legislative
Gross square footage	0	0	0	Approvals) - Specify:
Number of housing units	0	0	0	
Maximum height (in feet)	0	0	0	
TRANS	PORTATION			
ehicle trips per day	0	NA	NA	
Parking spaces	0	0	0	
WATER/V	VASTEWATE	₹		
Gallons/day (GPD) of water use	NA	NA	NA	
SPD water withdrawal	NA	NA	NA	
GPD wastewater generation/ reatment	NA	NA	NA	
ength of water/sewer mains in miles)	NA	NA	NA	
ONSERVATION LAND: Will the projections of any purpose not in according Yes (Specify ill it involve the release of any consestriction, or watershed preservation in Yes (Specify	vation restriction	sle 97?) [5	∂No	

RARE SPECIES: Does the project site include Estimated Hat Rare Species, or Exemplary Natural Communities?		f Rare Species, Vernal Pools, Priority Sites of
Yes (Specify	_)	⊠No
HISTORICAL /ARCHAEOLOGICAL RESOURCES: Does the in the State Register of Historic Place or the inventory of Historic Yes (Specify	ric ar)	nd Archaeological Assets of the Commonwealth? I⊠No
If yes, does the project involve any demolition or destruction or resources?	f any	listed or inventoried historic or archaeological
☐Yes (Specify)	⊠No
AREAS OF CRITICAL ENVIRONMENTAL CONCERN: is the Environmental Concern?		ect in or adjacent to an Area of Critical
Yes (Specify	_)	⊠No
PROJECT DESCRIPTION: The project description si	hould	include (a) a description of the project site

PROJECT DESCRIPTION: The project description should include **(a)** a description of the project site, **(b)** a description of both on-site and off-site alternatives and the impacts associated with each alternative, and **(c)** potential on-site and off-site mitigation measures for each alternative (*You may attach one additional page, if necessary.*)

This Project involves the limited removal of wetland soil and restoration of approximately 0.2 acres of wetland at three Areas of Concern (AOC) located within onsite wetlands as shown on the attached Figure 2A (taken from the NOI, January 2004). Two areas are located at storm water outfalls 001 and 002 (Areas A and B), and the third area is located down-gradient of outfall 002 (Area C). This work is being conducted in accordance with the requirements of the Massachusetts Department of Environmental Protection (MA DEP) per the Massachusetts Contingency Plan (MCP) in order to eliminate risk posed by inorganic contaminants (e.g. copper, lead and zinc) to ecological receptors in the area. A no action alternative was considered for these AOCs. However, no action would allow risk to ecological receptors to persist. Therefore, MADEP has required the removal of these impacted sediments and wetland soils. It is estimated that the remedial excavation and restoration activities will take approximately 3 weeks to complete. In addition, in order to minimize impacts and maximize the potential for a rapid restoration of wetland flora and fauna, the work activities are anticipated to be conducted in late winter/early spring prior to the 2004 growing season. The Project will remove approximately one foot of soil within a 0.2-acre area (350 cubic yards); and restore the disturbed wetland area.

Wetlands Protection Act Performance Standards will be met through the following methods:

- There will be no permanent hydrological changes;
- Best Management Practices will be utilized;
- •Mitigating measures will be employed to protect the interests of the Wetlands Protection Act;
- There will be no permanent loss of flood storage capacity;
- •There will be no permanent obstruction to flow by access road, assessment, or monitoring devices;
- Temporary structures will be removed within 30 days of the completion of the work. Temporary alterations
 to resource areas will be substantially restored to preexisting topography and hydrology. The disturbed
 areas will exhibit 75% vegetated cover within two seasons. Exposed soils will be stabilized in
 accordance with USDA standards.

The following describes the general sequence of construction activity and mitigation measures proposed to reduce any potential adverse effects associated with the work activity.

Prior to excavation activities, hay bales and silt fence will be installed to control potential erosion and sedimentation and protect adjacent or down-gradient wetland areas. Traffic controls such as cones, caution tape and orange snow fence will be used to define the work and staging areas, the excavated soils, and the dewatering area. Construction equipment will be routed around the work zones.

The staging area for the construction trailer and equipment storage will be located on the existing parking lot. In

order to minimize the extent of adverse effects of equipment access on bordering vegetated wetland and buffer zone, two access points were identified during the course of the wetland delineation and site surveys. Temporary equipment access routes will be limited to a gravel road approximately twelve feet wide and 4-inches thick. Temporary access in the wetland will be accomplished with the use of "Swamp Mats" to ensure safe and stable operation of equipment and to avoid ruts and sedimentation. These swamp mats distribute the load of the equipment and decrease the bearing pressure, thereby allowing the equipment to work on the surface of the soils without sinking.

Minor cutting activities will take place in the buffer zone of the wetland. We anticipate that all hardwoods and shrub species will regenerate basal sprouts following the cutting.

Prior to excavation of Areas A and B, berms will be constructed at the outfall areas to create a sump from which storm water can be pumped and re-directed to a downstream wetland location during excavation activities. A berm will also be constructed at the downstream limit of contaminated sediments in order to prevent water from the surrounding wetland from draining back into the area of sediment removal. In order to facilitate the removal of sediments, the standing water within the bermed area will be removed and pumped through a particulate filter prior to discharge at a downstream location in the wetland. Water will be pumped at a maximum rate of 50 gallons per minute. Engineering controls will be utilized to dissipate the energy of the water and prevent soil erosion or other disturbance of the wetland.

Prior to excavation of Area C, an "excavation containment berm" will be constructed around Area C in order to contain potentially sediment-laden water from leaving the excavation, and to prevent surrounding wetland water from draining back into the excavation. In order to facilitate the removal of soil, the standing water within the bermed area will be removed and pumped through a particulate filter prior to discharge at a downstream location in the wetland. Engineering controls will be utilized to dissipate the energy of the water and prevent soil erosion.

With erosion and sedimentation controls and dewatering provisions installed and functional, the top 12 inches of wetland soil will be excavated and transferred to the Excavated Material Staging Area for dewatering. Methods for sediment and soil dewatering/handling may include, but are not limited to "Filter Boxes", stockpiling in a temporary bermed area, and stabilizing with reagent. All water that is collected by the dewatering procedures will be transferred to a temporary holding tank (frac tank) to be located outside of the 100-foot buffer zone. This will allow for additional settling of sediment. It will then be transferred by pump through particulate filters to remove any remaining suspended sediment, and routed to the existing on-site groundwater treatment system.

The wetland restoration plan for the project has the goal of restoring the wetland with similar functional attributes of the undisturbed adjacent wetland. It is proposed that the planting of the wetland restoration area will take place in the early spring and that all wetland plant nursery stock and seed mix will be selected on basis of the existing vegetation species composition and density of the adjacent wetland. The restored wetland grade will be determined by an onsite pre-construction ground survey that will identify the appropriate base depth of the wetland with respect to hydrology. Wetland soil replacement will replicate the existing hummock-hollow topography observed throughout the wetland. In addition to the creation of the hummocks, decomposed woody debris will be placed in the wetland restoration area, to provide structure composition and germination substrate for plant species and potential wildlife habitat. The seed mix will be applied using a hydro-seeder in the early spring. Once the seed has been applied, a light mulch of clean straw mulch will be applied to the restoration surface.

A post-construction monitoring program of the restored wetland area for a period of two years is proposed to ensure that the area is responding positively to the restoration efforts, and to take measures to correct or enhance the area, if needed.

For a more detailed project description, including existing wetland community, best management practices, wetland planting plan, and post-construction monitoring plan, please see the attached Notice of Intent filed in North Reading, MA.