


REPORT

Building Demolition Alternative Report




Aerovox, Inc. Facility
New Bedford, Massachusetts

April 1998

TECHNICAL REPORT

Building Demolition Alternative Report



Aerovox, Inc. Facility
New Bedford, Massachusetts

April 1998

BBL

BLASLAND, BOUCK & LEE, INC.
engineers & scientists

6723 Towpath Road, P.O. Box 66
Syracuse, New York, 13214-0066
(315) 446-9120

Table of Contents

Section 1.	Introduction	1-1
	1.1 General	1-1
	1.2 Purpose and Scope	1-1
	1.3 Background Information	1-1
Section 2.	Summary of Investigation Activities	2-1
	2.1 General	2-1
	2.2 PCB Building Material/Equipment Investigation	2-1
	2.2.1 PCB Building Materials/Equipment Investigation Activities	2-1
	2.2.2 PCB Building Material/Equipment Investigation Results	2-2
	2.3 Soil Sampling Beneath Concrete Floor Slab	2-2
	2.3.1 Soil Sampling Activities Beneath Concrete Floor Slab	2-3
	2.3.2 Soil Sampling Results Beneath Concrete Floor Slab	2-3
	2.4 Surface Cleaning Pilot Study Results	2-3
Section 3.	Building Demolition Alternative	3-1
	3.1 General	3-1
	3.2 Building Demolition	3-1
Section 4.	Cost Estimate Summary	4-1
	4.1 Cost Estimate for Building Demolition Alternative	4-1
Section 5.	Schedule	5-1
	5.1 General	5-1
Tables	1 PCB Analytical Results: Full Core and Dust and Dirt Scrape Samples	
	2 PCB Analytical Results: Wipe Samples	
	3 Soil Sampling Results for Total PCBs Beneath Concrete Floor Slab	
	4 Building Demolition Alternative - Option 1 Cost Estimate	
	5 Building Demolition Alternative - Option 2 Cost Estimate	
	6 Building Demolition Alternative - Option 3 Cost Estimate	

Figures

- 1 Full Core and Dust and Dirt Sample Results
- 2 Wipe Sample Results
- 3 PCB Soil Sampling Results Beneath Concrete Floor Slab
- 4 Approximate Extent of Floor Slab to be Removed Under Option 2

Appendices

- A Analytical Data Report
- B Building Material Volume and Mass Calculations

1. Introduction

1.1 General

This report presents a description of the Building Demolition Alternative for the Aerovox, Inc. (Aerovox) facility located in New Bedford, Massachusetts. The Aerovox facility consists of one three-story building currently used to manufacture capacitors and related products. A technical description of the building demolition alternative is presented below, followed by a detailed cost estimate for implementing the building demolition alternative.

1.2 Purpose and Scope

The purpose of this report is to provide Aerovox with basic cost and technical information to facilitate a decision regarding the potential demolition of the building. The report considers above-grade and sub-grade building materials, but does not incorporate concerns, if any, with underground utilities, soils in the vicinity of the building and beneath the concrete floor slab, or ground water.

This report is organized into four sections. Section 1 presents general information, the purpose and scope of the report, and relevant background information including a summary of previous sampling events. Section 2 presents a summary of investigation activities conducted by BBL, including a PCB Building Material/Equipment Investigation, soil sampling activities conducted to characterize PCB concentrations in soil located directly beneath the concrete floor slab inside the building, and a preliminary surface cleaning pilot study. Section 3 presents a preliminary description of the Building Demolition Alternative. Section 4 presents estimated costs for implementing the Building Demolition Alternative. Section 5 presents an anticipated schedule for implementing the work activities associated with building demolition.

1.3 Background Information

The Aerovox facility building encompasses approximately 450,000 square feet and consists of a western section that contains two floors and an eastern section that contains three floors. The exterior walls of the building are brick while the roof is constructed of wood. The first floor in the western section of the building is estimated to be approximately 6 feet below grade while the first floor in the eastern section of the building is estimated to be approximately 1½ feet below grade. The first floor in both the eastern and western sections of the building is constructed of concrete. Structural components of the building include interior wood columns and steel I-beam floor joists. Wooden floors are present on the second and third floors of the eastern section of the building, and in a portion of the second floor of the western section of the building.

A soil and ground-water PCB investigation and remedial alternatives evaluation was completed in the mid-1980's. Exterior PCB-impacted soil was remediated via the installation of an asphalt cap. In June 1997, the United States Environmental Protection Agency (USEPA) conducted an inspection of the Aerovox building and collected 20 wood shaving samples from the floor of the capacitor impregnation tank room and collected oil samples from various oil storage tanks/degreaser operations for PCB analysis. The USEPA data indicated the presence of PCBs in the wood floor samples at concentrations greater than 50 parts per million (ppm). PCBs were not detected above laboratory detection limits in the oil samples collected from tanks/equipment at the Aerovox facility. In October 1997, a consultant for Aerovox (East Coast Engineering, Inc.) under USEPA oversight collected 93 standard wipe samples for PCB analysis. Ten duplicate wipe samples were also obtained and submitted to the USEPA. The analytical results indicated the presence of PCBs at concentrations greater than 10 micrograms (ug)/100 square centimeters (cm²) which is the Toxic Substance Control Act (TSCA) PCB Spill Policy cleanup objective for low- and high-contact interior surfaces. Figure 1 presents the results for samples collected by the USEPA during June 1997 and Figure 2 presents the wipe sample results from the October 1997 wipe sampling event.

2. Summary of Investigation Activities

2.1 General

This section presents a description of the PCB Building Material/Equipment Investigation conducted by BBL on November 24 and 25, 1997 and a description of soil sampling activities beneath the concrete floor slab conducted by BBL on February 11 and 12, 1998. This section also presents the results of a surface cleaning pilot study that was conducted to determine the effectiveness of surficial washing as a means of reducing PCB concentrations on non-porous surfaces. The PCB Building Material/Equipment Investigation, soil sampling beneath the concrete floor slab, and the surface cleaning pilot study are discussed below.

2.2 PCB Building Material/Equipment Investigation

The purpose of the PCB Building Material/Equipment Investigation was to supplement the existing PCB data base, determine the approximate extent of impacted building materials, develop information regarding the approximate quantities of different building materials, and characterize PCB concentrations on equipment surfaces inside the building. The PCB Building Materials/Equipment Investigation activities and results are discussed below.

2.2.1 PCB Building Materials/Equipment Investigation Activities

The PCB Building Material/Equipment Investigation consisted of the following activities:

- The collection of 17 full-core building material samples (wood, brick, and concrete) for PCB analysis;
- The collection of 12 composite scrape samples of dust/dirt from elevated horizontal surfaces for PCB analysis;
- The collection of 18 standard wipe samples from non-porous building material surfaces (tile floor, painted walls, steel surfaces, etc.) for PCB analysis;
- The collection of 13 standard wipe samples from the non-porous surfaces of select equipment; and
- The performance of a surficial cleaning method pilot study.

Sample locations were chosen to provide information regarding PCB concentrations in and on building materials that were not sampled previously. In addition, a select number of sample locations were chosen to correlate previous sample locations to confirm the previous data.

The PCB samples were containerized and shipped under chain of custody procedures to BBL's laboratory subcontractor, Galson Laboratories, Inc. (Galson) located in Syracuse, New York. Each sample was analyzed for PCBs using USEPA SW-846 Method 8082. Sample locations were tied to existing structures (i.e., columns, walls, etc.) and noted in the field log book.

In addition to the sampling activities, BBL also conducted a visual reconnaissance of the building to determine the following:

- Dimensions of existing building components including exterior and interior walls, floors, the roof, steel joints, and wood columns;
- The approximate extent of non-porous and porous surfaces;

-
- The approximate number of equipment pieces; and
 - The presence of potential asbestos-containing materials.

The results of the visual reconnaissance activities have been used to determine the approximate volume and weight of existing building components and non-porous surfaces in order to prepare cost estimates for the building demolition alternative, as discussed in Sections 3 and 4.

The results of the PCB Building Material/Equipment Investigation are presented below.

2.2.2 PCB Building Material/Equipment Investigation Results

Table 1 presents the analytical result for each full core sample and each dust/dirt scrape sample along with the sample identification number and building material type (wood, concrete, etc.). Table 2 presents the analytical results for each wipe sample collected from non-porous building materials, appurtenances, and equipment inside the building. The location of each wipe sample along with the associated PCB analytical result is shown on Figure 2. Analytical results for the laboratory analysis of the full-core samples, the dust and dirt samples, and the wipe samples are discussed below.

Full Core Samples

The analytical results indicate that the wood floor on the second and third floors of the eastern section of the building contains PCBs at concentrations greater than 50 ppm. Two of the three wood floor full core samples (i.e., samples 2-FC-4 and 2-FC-5) collected from the second floor in the western section of the building contained PCBs at concentrations greater than 50 ppm. One of the two concrete floor full core samples collected from the second floor in the western section of the building contained PCBs at concentrations greater than 50 ppm.

The analytical results indicate that PCBs were detected in full core samples collected from the brick exterior walls at concentrations ranging from 2.48 ppm to 26.4 ppm. The full core wood ceiling sample collected from the second floor ceiling (in the western section of the building) contained PCBs at a concentration of 28.3 ppm.

Dust and Dirt Samples

PCBs were detected in each of the 12 dust and dirt scrape samples at concentrations greater than 50 ppm.

Wipe Samples

Seventeen of the 18 wipe samples collected from non-porous building materials and appurtenances (electrical conduits and light fixtures) contained PCBs at concentrations greater than the TSCA Spill Cleanup Policy cleanup level of 10 ug/100 cm² for high- and low-contact surfaces. Ten of the 13 wipe samples collected from the surfaces of equipment at the Aerovox facility contained PCBs at concentrations greater than 10 ug/100 cm².

2.3 Soil Sampling Beneath Concrete Floor Slab

The purpose of the soil sampling activities beneath the concrete floor slab was to characterize PCB concentrations in soil located directly beneath the concrete floor slab inside the building. The soil sampling activities beneath the concrete floor slab and the sampling results are discussed below.

2.3.1 Soil Sampling Activities Beneath Concrete Floor Slab

The soil sampling activities beneath the concrete floor slab consisted of collecting 15 soil samples at a depths of 0 to 2 inches beneath the concrete slab for PCB analysis. In addition, soil samples were also collected at a depth of 2 to 6 inches beneath the concrete floor slab at 14 of the 15 soil sampling locations. The soil samples collected from the 2- to 6-inch depth interval were submitted to Galson and archived until the analytical results for the soil samples collected from the 0- to 2-inch depth interval were determined. The soil samples were containerized and shipped to Galson under chain of custody procedures for laboratory analysis for PCBs using USEPA SW-846 Method 8082. Sample locations were tied to existing columns and noted in the field log book. The results for the soil samples collected from beneath the concrete floor slab are presented below.

2.3.2 Soil Sampling Results Beneath Concrete Floor Slab

The analytical results indicate that 5 of the 14 soil samples collected from the 0- to 2-inch depth interval contained PCBs at concentrations greater than 50 ppm. Based on the analytical results for samples 1B6(0-2") and 1D7(0-2"), soil samples 1B6(2-6") and 1D7(2-6") (which were initially archived) were analyzed for PCBs using USEPA SW-846 Method 8082. The analytical results indicate that each of these samples contained PCBs at concentrations greater than 50 ppm. Table 3 presents the analytical results for each soil sample. The location of each soil sample along with the associated PCB analytical result is shown on Figure 3.

2.4 Surface Cleaning Pilot Study Results

BBL conducted two surficial cleaning pilot studies at the Aerovox facility in order to determine the effectiveness of surficial washing as a means of reducing PCB concentrations on non-porous surfaces. Each pilot study was conducted utilizing the following procedure:

- 1) A pre-cleaning wipe sample was collected from the select non-porous surface;
- 2) In an immediately adjacent location, the surface was cleaned using rags and a spray-on detergent (Knight's Super Spray Clean); and
- 3) A post-cleaning wipe sample was collected following the cleaning of the non-porous surface.

The first pilot study was conducted on the horizontal surface of a ceiling steel I-beam located on the first floor in the western section of the building near the lower pump room. The results of the first pilot study are as shown below.

Pre-Cleaning Wipe Sample	Post-Cleaning Wipe Sample
1-PSW-1	1-PSW-1A
Result: 520 ug/100 cm ²	Result: 226 ug/100 cm ²

The second pilot study was conducted on the steel diagonal plate floor covering located at the second floor receiving dock in the eastern section of the building. The results of the second pilot study are as shown below.

Pre-Cleaning Wipe Sample	Post-Cleaning Wipe Sample
2-PSW-1	2-PSW-1A
Result: 163 ug/100 cm ²	Result: 34 ug/100 cm ²

The results of the pilot studies indicate that a one-time surficial detergent washing did not achieve the TSCA PCB spill cleanup level of 10 ug/100 cm². Additional detergent washing will likely be required to accomplish the following:

- a. Determine how many washes it will take to achieve the cleanup objective; and
- b. Determine what PCB concentration can be achieved with a reasonable number of surface washes (i.e., three times).

The second pilot study results indicate that detergent washing may achieve a non-porous surface PCB concentration of less than 100 ug/100 cm² which is the typical cleanup requirement for steel prior to being accepted for disposal (smelting) at a steel recycling facility.

3. Building Demolition Alternative

3.1 General

This section presents a description of the Building Demolition Alternative developed by BBL based on the analytical data generated to date and based on our past experience with building remediation. A description of the Building Demolition Alternative is presented below.

3.2 Building Demolition

Under this alternative, the building would be demolished and the site would be restored by installing an impermeable liner and an asphalt cap following placement of backfill materials at the former location of the building. The Building Demolition Alternative would consist of the seven major work activities listed below:

- Work Activity 1 - Additional Building Characterization Sampling;
- Work Activity 2 - Equipment/Appurtenances Inventory;
- Work Activity 3 - Pre-Demolition Cleaning;
- Work Activity 4 - Post-Cleaning Verification Sampling;
- Work Activity 5 - Utility Modifications and Removal;
- Work Activity 6 - Building Demolition and Disposal; and
- Work Activity 7 - Site Restoration/Asphalt Cap Construction.

These work activities are discussed below.

Work Activity 1 - Additional Building Characterization

Prior to implementing building demolition activities, additional sampling would be conducted to confirm that the brick walls in the pump room located on the first floor and the brick walls in the impregnation room (tank room) located on the second floor directly above the pump room do not contain PCBs at concentrations greater than or equal to 50 ppm. The additional sampling work would involve collecting an appropriate number of discrete core samples from the brick walls in these two rooms (i.e., six samples) for laboratory analysis for PCBs.

If the analytical results of the core samples indicate that PCBs are present at concentrations less than 50 ppm, the brick walls would be handled with other non-TSCA demolition debris. However, if the analytical results of the core samples indicate that PCBs are present at concentrations greater than or equal to 50 ppm, the brick walls would require disposal at a TSCA landfill.

Work Activity 2 - Equipment/Appurtenances Inventory

Under this work activity, a detailed inventory of equipment/appurtenances at the facility (both inside and outside the building) would be developed. In addition to listing equipment/appurtenances, the inventory would identify which equipment/appurtenances would be transferred from the facility and returned to commerce at a proposed new facility, which equipment/appurtenances would be offered for sale, and which equipment/ appurtenances would be scrapped. In order to develop the inventory, the following work would be conducted:

- A site reconnaissance to identify each piece of equipment/appurtenance in its current location, record applicable information from manufacturer's plates on the equipment/appurtenances, and assess the condition of the equipment/appurtenances; and

-
- A review of applicable records pertaining to each piece of equipment (if available) and coordination with engineering/operations personnel at the facility. The review/coordination work would be conducted in an effort to identify the age and repair history of the equipment/appurtenances, to estimate the market value for the equipment/appurtenances, and to determine the role (if any) for the the equipment/appurtenances in future manufacturing operations.

Aerovox would be responsible for determining which equipment/appurtenances would be retained for future use at a new manufacturing location, which equipment/appurtenances would be offered for sale, and which equipment/appurtenances would be scrapped.

Work Activity 3 - Pre-Demolition Cleaning

This work activity would consist of washing interior horizontal surfaces with detergent to remove PCB-containing dust and dirt in order to facilitate general demolition of the building. The pre-demolition cleaning would involve the cleaning of the steel I-beams, HVAC duct work, and other metal surfaces to reduce PCB concentrations to less than 100 ug/100 cm² in order to allow for the removal and disposal of the material at a steel smelting facility.

As part of the pre-demolition cleaning activities, equipment surfaces containing PCBs at concentrations greater than 10 ug/100 cm² would require cleaning prior to transferring the equipment off-site.

Based on the presence of vinyl floor tile, pipe insulation materials, and boiler insulation materials within the building that may potentially contain asbestos, an asbestos survey will be conducted to determine if asbestos abatement is required prior to building demolition. For the purpose of this report we have assumed that these materials contain asbestos and would be removed as part of the pre-demolition cleaning activities.

Work Activity 4 - Post-Cleaning Verification Sampling

Following completion of the pre-demolition cleaning activities, a visual inspection will be conducted to confirm that visible dust and dirt has been removed followed by a post-cleaning verification wipe sampling program to:

- Confirm that metal surfaces scheduled for smelting do not contain PCBs at concentrations greater than 100 ug/100 cm²; and
- Confirm that equipment surfaces scheduled for reuse do not contain PCBs at concentrations greater than 10 ug/100 cm².

Work Activity 5 - Utility Modifications and Removal

Upon completion of the post-cleaning verification sampling activities, modifications to existing utilities and removal of interior utilities would occur. The utility modifications would include the following:

- Disconnection and plugging of sanitary sewer piping and any additional drain piping;
- Disconnection of the existing potable water supply; and
- Disconnection of electrical services.

The following utility removal actions would also be conducted:

- Removal of electrical equipment, boilers, and compressors;

-
- Removal of light fixtures (fluorescent light ballasts may contain PCBs);
 - Removal of fire protection and potable water piping; and
 - Removal of HVAC system components (excluding steel duct work).

Work Activity 6 - Building Demolition and Disposal

As part of this work activity, the building would be demolished and concrete/brick debris generated by demolition of the building which does not contain PCBs at concentrations greater than or equal to 50 ppm would either be transported for off-site disposal or used as backfill on-site depending on which of the following options is selected: 1) leave the first floor concrete slab in-place, 2) remove a portion of the first floor concrete slab; or 3) remove the entire first floor concrete slab (details associated with the demolition work to be conducted under each of these options are presented below). Materials within the building which do not contain PCBs at concentrations greater than or equal to 50 ppm have been identified based on the analytical results for samples previously collected. The actual amount of building materials which do not contain PCBs at concentrations greater than or equal to 50 ppm may decrease (resulting in an increase in TSCA-regulated building materials) depending on the results of additional sampling that will be conducted prior to the building demolition within the pump room and the tank room.

The demolition Contractor will be required to comply with a set of special conditions specific to project. The special conditions will include, but not be limited to, the following plans and procedures:

- Air monitoring procedures;
- Dust control procedures;
- Surface water control procedures;
- Equipment decontamination procedures;
- Health and safety plan; and
- Contingency plans.

A set of the special conditions will be provided to the USEPA prior to implementing the demolition activities. A description of the work to be conducted by the Contractor under demolition Options 1-3 is presented below.

Option 1: Leave the First Floor Concrete Slab In-Place

Under this option, the wood and concrete floors that contain PCBs at concentrations greater than or equal to 50 ppm (excluding the first floor concrete slab) would be removed from the building and transported for off-site disposal at a TSCA landfill permitted to accept debris containing PCBs at concentrations greater than or equal to 50 ppm. Based on a preliminary review of the building, BBL has assumed that the wood and concrete floors could be removed (prior to demolition of the entire building) without jeopardizing the structural integrity of the building. However, before preparing a Contractor scope of work for the building demolition, a more comprehensive structural review of the building will be conducted by a Licensed Professional Engineer experienced in performing structural evaluations in order to confirm that the wood and concrete floors can be removed without impacting the structural integrity of the building shell prior to general demolition activities. The Engineer will also provide recommendations for temporary structural support that may be needed during the floor removal activities.

Following removal of the wood and concrete floors that contain PCBs at concentrations greater than or equal to 50 ppm, the building would be demolished using traditional demolition techniques (i.e., a wrecking ball, excavators). Dust control measures will be implemented to minimize dust levels generated by the demolition work. The actual techniques/methods to be employed will be recommended by the demolition Contractor and

reviewed and approved by the Engineer. The selected Contractor would be required to furnish details regarding demolition techniques/methods and the locations of debris staging/loading areas.

Debris (concrete, wood, brick) which does not contain PCBs at concentrations greater than or equal to 50 ppm would be transported for off-site disposal at a non-TSCA landfill permitted to accept the debris. Steel building components and associated metal materials generated during the demolition activities which do not contain PCBs on the surfaces at concentrations greater than or equal to 100 ug/cm² (as determined by verification sampling conducted under Work Activity 4) would be segregated and transported off-site for smelting. We have assumed that the pre-demolition cleaning activities under Work Activity 3 will be successful in removing dust/dirt from the steel building components and associated metal material surfaces so that PCBs will not be detected in post-cleaning verification wipe samples at concentrations greater than or equal to 100 ug/cm². However, if the concentration of PCBs remaining on the steel building components and associated metal material surfaces following cleaning is greater than or equal to 100 ug/cm², then the steel building components and associated metal materials will be transported for off-site disposal as a TSCA waste. Following removal of the debris generated by the building demolition, clean backfill obtained from an off-site source would be placed, graded, and compacted above the remaining building floor slab to within one foot of the existing grade which surrounds the building. After compacting the backfill, an asphalt cap would be installed as described under Work Activity 7 below.

Option 2: Remove a Portion of the First Floor Concrete Slab

Under this option, the wood and concrete floors that contain PCBs at concentrations greater than or equal to 50 ppm (including a portion of the first floor concrete slab from areas potentially containing PCB concentrations greater than 50 ppm) would be removed from the building and transported for off-site disposal at a TSCA landfill permitted to accept debris containing PCBs at concentrations greater than or equal to 50 ppm. The portion of the first floor concrete slab to be removed for off-site disposal under this option is shown on Figure 4. Based on a preliminary review of the building, BBL has assumed that the wood and concrete floors could be removed (prior to demolition of the entire building) without jeopardizing the structural integrity of the building. However, before preparing a Contractor scope of work for the building demolition, a more comprehensive structural review of the building will be conducted by a Licensed Professional Engineer experienced in performing structural evaluations in order to confirm that the wood and concrete floors can be removed without impacting the structural integrity of the building shell prior to general demolition activities. The Engineer will also provide recommendations for temporary structural support that may be needed during the floor removal activities.

Following removal of the wood and concrete floors that contain PCBs at concentrations greater than or equal to 50 ppm, the building would be demolished using traditional demolition techniques (i.e., a wrecking ball, excavators). Dust control measures will be implemented to minimize dust levels generated by the demolition work. The actual techniques/methods to be employed will be recommended by the demolition Contractor and reviewed and approved by the Engineer. The selected Contractor would be required to furnish details regarding demolition techniques/methods and the locations of debris staging/loading areas.

Debris generated by the building demolition which does not contain PCBs at concentrations greater than or equal to 50 ppm (excluding wood, drywall materials, or steel) would be placed as backfill within the below-grade portions of the first floor area. Additional backfill, consisting of a clean sand/gravel obtained from an off-site source, would be mixed in with the debris and placed, graded, and compacted to within one foot of the existing grade which surrounds the building. Debris, consisting of wood and drywall, would be transported for off-site disposal at a non-TSCA landfill. Steel building components and associated metal materials generated during the demolition activities which do not contain PCBs on the surfaces at concentrations greater than or equal to 100

ug/cm² (as determined by verification sampling conducted under Work Activity 4) would be segregated and transported off-site for smelting. We have assumed that the pre-demolition cleaning activities under Work Activity 3 will be successful in removing dust/dirt from the steel building components and associated metal material surfaces so that PCBs will not be detected in post-cleaning verification wipe samples at concentrations greater than or equal to 100 ug/cm². However, if the concentration of PCBs remaining on the steel building components and associated metal material surfaces following cleaning is greater than or equal to 100 ug/cm², then the steel building components and associated metal materials will be transported for off-site disposal as a TSCA waste. After placing, grading, and compacting the backfill within the below grade portions of the first floor area, an asphalt cap would be installed as described under Work Activity 7.

Option 3: Remove the Entire First Floor Concrete Slab

Under this option, the wood and concrete floors that contain PCBs at concentrations greater than or equal to 50 ppm (including the entire portion of the first floor concrete slab) would be removed from the building and transported for off-site disposal at a TSCA landfill permitted to accept debris containing PCBs at concentrations greater than or equal to 50 ppm. Based on a preliminary review of the building, BBL has assumed that the wood and concrete floors could be removed (prior to demolition of the entire building) without jeopardizing the structural integrity of the building. However, before preparing a Contractor scope of work for the building demolition, a more comprehensive structural review of the building will be conducted by a Licensed Professional Engineer experienced in performing structural evaluations in order to confirm that the wood and concrete floors can be removed without impacting the structural integrity of the building shell prior to general demolition activities. The Engineer will also provide recommendations for temporary structural support that may be needed during the floor removal activities.

Following removal of the wood and concrete floors that contain PCBs at concentrations greater than or equal to 50 ppm, the building would be demolished using traditional demolition techniques (i.e., a wrecking ball, excavators). Dust control measures will be implemented to minimize dust levels generated by the demolition work. The actual techniques/methods to be employed will be recommended by the demolition Contractor and reviewed and approved by the Engineer. The selected Contractor would be required to furnish details regarding demolition techniques/methods and the locations of debris staging/loading areas.

Debris generated by the building demolition which does not contain PCBs at concentrations greater than or equal to 50 ppm (excluding wood, drywall materials, or steel) would be placed as backfill within the below-grade portions of the first floor area. Additional backfill, consisting of a clean sand/gravel obtained from an off-site source, would be mixed in with the debris and placed, graded, and compacted to within one foot of the existing grade which surrounds the building. Debris, consisting of wood and drywall, would be transported for off-site disposal at a non-TSCA landfill. Steel building components and associated metal materials generated during the demolition activities which do not contain PCBs on the surfaces at concentrations greater than or equal to 100 ug/cm² (as determined by verification sampling conducted under Work Activity 4) would be segregated and transported off-site for smelting. We have assumed that the pre-demolition cleaning activities under Work Activity 3 will be successful in removing dust/dirt from the steel building components and associated metal material surfaces so that PCBs will not be detected in post-cleaning verification wipe samples at concentrations greater than or equal to 100 ug/cm². However, if the concentration of PCBs remaining on the steel building components and associated metal material surfaces following cleaning is greater than or equal to 100 ug/cm², then the steel building components and associated metal materials will be transported for off-site disposal as a TSCA waste. After placing, grading, and compacting the backfill within the below grade portions of the first floor area, an asphalt cap would be installed as described under Work Activity 7.

Work Activity 7 - Site Restoration/Asphalt Cap Construction

Under this work activity, a capping system would be constructed over the area where the building was located following the placement and compaction of backfill over the area. The capping system would be constructed in accordance with the precedent that was established for remediation of PCB-impacted soils located outside the building footprint (to the north and east of the building). The capping system would consist of the following materials (referenced, in order, from the surface to the base of the capping system):

- A 1½-inch thick bituminous concrete wearing surface over a 2½-inch thick bituminous concrete base course;
- An 8-inch subbase course to provide bearing support for vehicles which will be parked on the bituminous concrete surface. The subbase course would consist of approximately 6 inches of run-of-crush stone over approximately 2 inches of sand. The sand would serve as a protective barrier to help prevent the underlying materials from being damaged during placement of the run-of-crush; and
- A geosynthetic drainage composite overlying a 40 mil impermeable PVC or HDPE membrane. The purpose of the geosynthetic composite would be to convey water (which may penetrate the bituminous concrete surface and would otherwise be trapped above the impermeable PVC or HDPE membrane) away from the capping system in an effort to prevent premature failure of the bituminous concrete resulting from frost action.

4. Cost Estimate Summary

4.1 Cost Estimate for Building Demolition Alternative

This section presents a summary of the estimated cost for the Building Demolition Alternative. The estimated cost for each Building Demolition Option is presented below.

Building Demolition Option	Cost Estimate
Building Demolition Alternative Option #1	\$7,400,000
Building Demolition Alternative Option #2	\$8,700,000
Building Demolition Alternative Option #3	\$10,300,000

The cost estimates are based on vendor quotes, past remedial costs, and BBL's experience with building demolition projects. Major assumptions that were made in developing the cost estimates for the Building Demolition Alternative under Options 1, 2, and 3 are listed below.

- 1) Double hand washing with detergent will reduce the concentration of PCBs on metal surfaces to less than 100 ug/100 cm².
- 2) Repeated rounds of verification sampling of metal surfaces will not be required.
- 3) The wood flooring in the eastern section of the building and concrete on the second floor of the western section of the building can be removed without jeopardizing the structural stability of the building.
- 4) Options for handling the first floor concrete slab will be acceptable to USEPA Region 1.
- 5) The cost of the asbestos removal and disposal program, which is of unknown extent at this time, will not exceed \$100,000.

Additional assumptions made in developing the cost estimates for the building demolition alternative under Options 1, 2, and 3 are presented in Tables 4, 5, and 6 (respectively) along with a detailed breakdown of the estimated costs.

5. Schedule

5.1 General

This section presents an approximate schedule for implementing the Building Demolition Alternative (assumed to be the same under each demolition option). The approximate schedule for implementing the building demolition work activities is presented below.

Work Activity	Approximate Duration
Work Activity 1 - Additional Building Characterization Sampling	2 days
Work Activity 2 - Equipment/Appurtenances Inventory	2 weeks
Work Activity 3 - Pre-Demolition Cleaning	6 weeks
Work Activity 4 - Post-Cleaning Verification Sampling	
Work Activity 5 - Utility Modifications and Removal	4 weeks
Work Activity 6 - Building Demolition and Disposal	16 weeks
Work Activity 7 - Site Restoration	4 weeks

The actual schedule for completing each work activity will be dependent upon the demolition Contractor's schedule, demolition techniques, the amount of asbestos removal required, the extent of utility modifications and removal necessary, and USEPA approval of the building demolition option selected by Aerovox.

Tables

BLASLAND, BOUCK & LEE, INC.
engineers & scientists

Table 1

Aerovox, Inc. Facility
New Bedford, Massachusetts

PCB Analytical Results
Full Core and Dust & Dirt Scrape Samples

Sample Type	Surface Material	Sample I.D.	PCBs Concentration ⁽¹⁾ [ppm]
First Floor - Eastern Section			
Full Core	Brick Wall (painted)	1-WC-1	7.4
Scrape	Composite	1-DD-1	880.0
Scrape	Composite	1-DD-2	121.0
Scrape	Composite	1-DD-3	420.0
First Floor - Across Section			
Scrape	Composite	1-DD-4	2010.0
Scrape	Composite	1-DD-5	950.0
Scrape	Composite	1-DD-6	268.0
Second Floor - Eastern Section			
Full Core	Wood floor (stained)	2-FC-1	1,900.0
Full Core	Wood floor (stained)	2-FC-2	5,600.0
Full Core	Wood floor (stained)	2-FC-3	106.0
Scrape	Composite	2-DD-3	260.0
Scrape	Composite	2-DD-4	490.0
Full Core	Brick wall (painted)	2-WC-3	8.0
Full Core	Brick wall (painted)	2-WC-4	2.5
Second Floor - Western Section			
Full Core	Wood floor (stained)	2-FC-4	145.00
Full Core	Wood floor (stained)	2-FC-5	56,000.0
Full Core	Wood floor (stained)	2-FC-6	28.0
Full Core	Concrete floor (stained)	2-FC-7	12.7
Full Core	Concrete floor (stained)	2-FC-8	156.0
Full Core	Ceiling beam (painted)	2-CC-1	28.3
Scrape	Composite	2-DD-1	1,020.0

*Table 1
(Cont'd)
Aerovox, Inc. Facility
New Bedford, Massachusetts*

*PCB Analytical Results
Full Core and Dust & Dirt Scrape Samples*

Sample Type	Surface Material	Sample I.D.	PCBs Concentration⁽¹⁾ [ppm]
Full Core	Brick Wall (painted)	2-WC-1	3.6
Full Core	Brick wall (painted)	2-WC-2	26.4
Second Floor - Across Sections			
Scrape	Composite	2-DD-2	300.0
Third Floor - Eastern Section			
Full Core	Wood floor (stained)	3-FC-1	86.0
Full Core	Brick wall (stained)	3-WC-1	2.48
Full Core	Wood floor (stained)	3-FC-2	204.0
Scrape	Composite	3-DD-1	1,170.0
Scrape	Composite	3-DD-2	470.0

NOTES:

1. ⁽¹⁾ - Concentrations are given for total PCBs in parts per million (ppm).
2. < - Indicates the compound was analyzed for but not detected. The associated value is the laboratory detection limit.
3. Values in bold exceed 50 ppm.

Table 2

Aerovox, Inc. Facility
New Bedford, Massachusetts

PCB Analytical Results
Wipe Samples

Surface Material	Sample I.D.	PCBs Concentration ⁽¹⁾ [ng/100cm ²]
First Floor - Eastern Section		
Concrete floor (painted)	1-FW-1	18.0
Top of electrical duct. Horizontal steel surface (painted).	1-AW-2	20.8
Concrete floor (painted)	1-FW-3	350.0
Brick wall (painted)	1-WW-4	15.4
Concrete floor (painted)	1-FW-5	59.0
Top of start/stop panel of air compressor. Horizontal metal surface (painted).	1-EW-1	66.0
Top of horizontal metal plate (painted).	1-EW-2	330.0
Side of drying oven # 4. Horizontal metal surface (painted).	1-EW-3	13.7
Side of rear base leg of federal press. Horizontal metal surface (painted).	1-EW-4	199.0
First Floor - Western Section		
Wood column (painted). Vertical surface.	1-AW-6	10.5
Elevated light fixture. Horizontal steel surface (painted).	1-AW-7	84.0
Inside left door of despatch oven. Vertical metal surface (unpainted).	1-EW-5	<2.5
"I" beam. Horizontal painted steel surface (pre-clean)	1-PSW-1	520.0
"I" beam. Horizontal painted steel surface (post-clean: vacuumed).	1-PSW-1A	226.0
Second Floor - Eastern Section		
Wood floor	2-FW-4	17.8
Tile floor	2-FW-5	14.8
Tile floor	2-FW-6	14.6
Tile floor	2-FW-7	3.3
Top of stainless steel horizontal surface.	2-EW-2	217.0

*Table 2
(Cont'd)
Aerovox, Inc. Facility
New Bedford, Massachusetts*

***PCB Analytical Results
Wipe Samples***

Surface Material	Sample I.D.	PCBs Concentration ⁽¹⁾ [ug/100cm ²]
Top of machine housing. Horizontal metal surface (painted).	2-EW-3	2.5
Horizontal diamond steel plate (pre-clean).	2-PSW-1	163.0
Horizontal diamond steel plate (post-clean: washed)	2-PSW-1A	34.0
Second Floor - Western Section		
Top of electrical box. Horizontal steel surface (painted).	2-AW-2	235.0
Wood floor (painted)	2-FW-3	90.0
Top of electrical box. Horizontal steel surface (painted).	2-AW-1	320.0
Base of press. Horizontal metal surface (painted).	2-EW-1	16.0
Third Floor - Eastern Section		
Tile floor	3-FW-1	22.6
Tile floor	3-FW-2	176.0
Tile floor	3-FW-3	98.0
Tile floor	3-FW-4	30.0
Top of assembly machine. Horizontal metal surface (painted).	3-EW-1	15.2
Top of gear housing of lead welding machine. Horizontal metal surface (painted).	3-EW-2	11.9
Top shelf of domino ink jet. Horizontal metal surface (painted).	3-EW-3	265.0
Top of base unit of metal winder. Horizontal metal surface (painted).	3-EW-4	68.0
Top of test/sort machine. Horizontal metal surface (painted).	3-EW-5	<2.5

NOTES:

1. ⁽¹⁾ - Concentrations are given for total PCBs in micrograms per 100 cm².
2. < - Indicates the compound was analyzed for but not detected. The associated value is the laboratory detection limit.
3. Values in bold exceed 10 ug/100 cm².

Table 4

Aerovox, Inc. Facility
New Bedford, Massachusetts

Building Demolition Alternative - Option #1

Cost Estimate

- Conduct additional building characterization sampling
- Conduct inventory of equipment/appurtenances
- Clean materials and equipment prior to demolition
- Dispose of materials ≥ 50 ppm PCBs at TSCA landfill
- Dispose of materials < 50 ppm PCBs at non-TSCA landfill
- Clean steel to < 100 ug/100 cm² PCBs for disposal at a smelting facility
- Leave first floor concrete slab in-place
- Place and compact backfill material above floor slab
- Install asphalt cap over the backfill

Work Activities		Quantity	Units	Unit/Cost	Total
1. Additional Building Characterization Sampling					
A.	Sampling and analysis of brick walls in Pump Room and Tank Room for PCBs	1	LS	\$2,500	\$2,500
B.	RCRA characterization sampling	1	LS	\$20,000	\$20,000
Subtotal Additional Building Characterization Sampling:					\$22,500
2. Equipment/Appurtenances Inventory					
A.	Conduct equipment/appurtenances inventory. Includes site reconnaissance activities, reviewing documentation for equipment/appurtenances, and meeting with an Aerovox operations personnel.	1	LS	\$4,500	\$4,500
Subtotal Equipment/Appurtenances Inventory:					\$4,500
3. Pre-Demolition Cleaning					
A.	Hand-wash interior surfaces to remove visible dust and dirt and to clean steel surfaces to ≤ 100 ug/100 cm ² . Includes disposal of cleaning water, dirt, and dust.	450,500	SF	\$2/SF	\$901,000
B.	Hand-wash equipment surfaces to < 10 ug/100 cm ² . Includes disposal of cleaning water, dirt, and dust.	200	EA	\$250/EA	\$50,000
C.	Asbestos Removal and Disposal	1	LS	\$100,000	\$100,000
Subtotal Pre-Demolition Cleaning:					\$1,051,000

Table 4
(Cont'd)
Aerovox, Inc. Facility
New Bedford, Massachusetts

Building Demolition Alternative - Option #1

Cost Estimate

Work Activities		Quantity	Units	Unit/Cost	Total
4. Post-Cleaning Verification Sampling					
A.	Post-cleaning verification sampling for building materials	1	LS	\$50,000	\$50,000
B.	Post-cleaning verification sampling for equipment	1	LS	\$45,000	\$45,000
Subtotal Post-Cleaning Verification Sampling:					\$95,000
5. Utility Modifications and Removal					
A.	Utility modifications, removal, and disposal prior to building demolition.	1	LS	\$100,000	\$100,000
Subtotal Utility Modifications and Removal:					\$100,000
6. Building Demolition and Disposal (Excluding Concrete Floor at Grade)					
A.	Removal of wood floor (TSCA material)	235,800	SF	\$5/SF	\$1,179,000
B.	Removal of concrete floor above first floor level (TSCA material)	15,000	SF	\$5.50/SF	\$82,500
C.	Building demolition	6,703,000	CF	\$0.23/CF	\$1,541,690
D.	Transportation and disposal of demolition debris:				
	- to TSCA landfill (mainly wood and concrete floor materials)	2,000	Ton	\$200/Ton	\$400,000
	- to non-TSCA landfill (mainly brick, wood, and drywall)	6,250	Ton	\$50/Ton	\$312,500
	- to steel smelting facility (mainly "I"-beams)	1,225	Ton	\$10/Ton	\$12,250
Subtotal Demolition and Disposal:					\$3,527,940
7. Site Restoration/Asphalt Cap Construction					
A.	Placement and compaction of backfill over the concrete floor slab	22,400	CY	\$13.50/CY	\$302,400
B.	40 mil PVC liner	182,133	SF	\$0.34/SF	\$61,925
C.	Geosynthetic drainage composite	182,133	SF	\$1.40/SF	\$254,986
D.	2" Sand/gravel layer	1,124	CY	\$13.00/CY	\$14,612

*Table 4
(Cont'd)
Aerovox, Inc. Facility
New Bedford, Massachusetts*

Building Demolition Alternative - Option #1

Cost Estimate

Work Activities		Quantity	Units	Unit/Cost	Total
E.	6" Run-of-crush stone layer	3,373	CY	\$18.47/CY	\$62,299
F.	2½" Bituminous concrete base course	20,237	SY	\$4.50/SY	\$91,067
G.	1½" Bituminous concrete wearing surface	20,237	SY	\$3.30/SY	\$66,782
Subtotal Site Restoration/Asphalt Cap Construction					\$854,071
Subtotal Work Activities # 1 through #7:					\$5,655,011
Engineering, Administrative, and Legal Fees (10%):					\$565,501
Contingency (20%):					\$1,131,002
Total Estimated Cost:					\$7,351,514
Rounded To:					\$7,400,000

Notes:

1. Costs are based on contractor estimates from previous projects and BBL's experience.
2. Transportation and disposal costs are based on verbal quotations received in December 1997 from Chemical Waste Management, Inc., and Laidlaw PCB Services.
3. Volume, area, and mass calculations were conducted using the tables and calculations presented in Appendix B.

Assnptions:

The assumptions below are listed in order by each work activity.

- 1A. Sampling and analysis cost estimate includes costs to collect up to 6 discrete full core samples from brick walls in the Pump Room and Tank Room for laboratory analysis for PCBs on a 24-hour turnaround basis.
- 1B. RCRA characterization sampling cost estimate includes costs for up to 20 building material core samples for laboratory analysis for corrosivity, ignitability, reactivity, and Toxicity Characteristic Leaching Procedure (TCLP) volatile organic compounds (VOCs), TCLP semi-volatile organic compounds (SVOCs), and TCLP metals on a 5-day turnaround basis.
- 2A. Conduct equipment/appurtenances inventory cost estimate includes costs for conducting site reconnaissance activities, reviewing equipment/appurtenances documentation, and meeting with Aerovox facilities personnel to determine equipment/appurtenances (both inside and outside the building) which would be returned to commerce and equipment/appurtenances which would be scrapped.

*Table 4
(Cont'd)
Aerovox, Inc. Facility
New Bedford, Massachusetts*

Building Demolition Alternative - Option #1

Cost Estimate

- 3A. Hand-wash interior surfaces cost estimate includes costs for washing interior horizontal surfaces (including steel beams/columns and HVAC duct work) using detergent and rags to remove visible dust and dirt. Cost includes disposal of cleaning water, rags, dirt, and dust as TSCA waste. Pre-building demolition cleaning area is based on the area of each floor level.
- 3B. Hand-wash equipment cost estimate includes costs for washing equipment using detergent and rags to remove visible dust and dirt. Cost includes disposal of cleaning water, rags, dirt, and dust as TSCA waste.
- 3C. Asbestos removal and disposal cost estimate includes costs for notifications, posting, permitting, air monitoring, recordkeeping, protective equipment, and removal and off-site disposal of the asbestos-containing materials in an approved non-hazardous waste landfill.
- 4A. Post-cleaning verification sampling for building materials cost estimate includes costs to collect verification wipe samples for laboratory analysis to confirm that interior building material surfaces (including steel and duct work) do not contain PCBs at concentrations greater than or equal to 100ug/cm².
- 4B. Post-cleaning verification sampling for equipment cost estimate includes costs to collect verification wipe samples for laboratory analysis to confirm that equipment surfaces do not contain PCBs at concentrations greater than or equal to 10ug/cm².
- 5A. Utility modifications, removal, and disposal cost estimate includes disconnecting electrical services; disconnecting the existing potable water supply; plugging sanitary sewer piping/floor drains; removing electrical equipment, boilers, and compressors; removing light fixtures; removing the fire protection and potable water supply piping; and removing HVAC system components.
- 6A. Removal of wood floor cost estimate includes costs for removing wood floors which contain PCBs at concentrations ≥ 50 ppm. Cost estimate assumes that the wood floors would be removed prior to demolition without affecting the structural integrity of the building.
- 6B. Removal of concrete floor above first floor level cost estimate includes costs for removing the concrete floor (within the second level of the western section of the building) which contains PCBs at concentrations ≥ 50 ppm. Cost estimate assumes that the concrete floor would be removed prior to building demolition without affecting the structural integrity of the building. Cost estimate assumes that the concrete floor slab located on the first level will remain in-place.
- 6C. Building demolition cost estimate includes costs for the demolition of the remaining portion of the building above the floor slab at grade. Demolition would be conducted following wood and concrete floor removal using conventional demolition techniques (i.e., wrecking ball, excavators).
- 6D. Transportation and disposal cost estimate includes costs for transportation and disposal of TSCA and non-TSCA material generated during the demolition activities. Cost estimate assumes that material generated during the wood and concrete floor removal activities (containing PCBs at concentrations ≥ 50 ppm) would be disposed at a TSCA facility. Cost estimate assumes that wood and drywall materials generated under the building demolition cost estimate (excluding steel materials) would be disposed at a non-TSCA landfill. Cost estimate assumes that steel materials will be disposed at a steel smelting facility and that the value of the steel will off-set the smelting

*Table 4
(Cont'd)
Aerovox, Inc. Facility
New Bedford, Massachusetts*

Building Demolition Alternative - Option #1

Cost Estimate

costs. Cost estimate for steel to smelting facility only includes costs for transportation.

- 7A. Placement and compaction of backfill cost estimate includes costs for providing, placing, and compacting imported clean backfill material (sand/unwashed gravel) over the first floor concrete floor slab to within one foot of existing grade.

- 7B-G. Asphalt cap construction cost estimate includes costs for installing a capping system constructed of a 1½ inch thick bituminous concrete wearing surface, a 2½ inch thick bituminous concrete base course, an 8 inch subbase (consisting of 6 inches of run-of-crush stone and 2 inches of sand), a geosynthetic drainage composite, and a 40 mil impermeable PVC or HDPE membrane.

Table 5

Aerovox, Inc. Facility
New Bedford, Massachusetts

Building Demolition Alternative - Option #2

Cost Estimate

- Conduct additional building characterization sampling
- Conduct inventory of equipment/appurtenances
- Clean materials and equipment prior to demolition
- Dispose of materials ≥ 50 ppm PCBs at TSCA landfill
- Disposal of wood materials < 50 ppm PCBs at non-TSCA landfill
- Clean steel to < 100 ug/100 cm² PCBs for disposal at a smelting facility
- Remove portions of the first floor concrete slab
- Backfill above the removed/remaining concrete floor slab using demolition materials < 50 ppm PCBs and imported clean backfill
- Install asphalt cap over the backfill

Work Activities		Quantity	Units	Unit/Cost	Total
1. Additional Building Characterization Sampling					
A.	Sampling and analysis of brick walls in Pump Room and Tank Room for PCBs	1	LS	\$2,500	\$2,500
B.	RCRA Characterization Sampling	1	LS	\$20,000	\$20,000
Subtotal Additional Building Characterization Sampling:					\$22,500
2. Equipment/Appurtenances Inventory					
A.	Conduct equipment/appurtenances inventory. Includes site reconnaissance activities, reviewing documentation for equipment/appurtenances, and meeting with an Aerovox operations personnel.	1	LS	\$4,500	\$4,500
Subtotal Equipment/Appurtenances Inventory:					\$4,500
3. Pre-Demolition Cleaning					
A.	Hand-wash interior surfaces to remove visible dust and dirt and to clean steel surfaces to ≤ 100 ug/100 cm ² . Includes disposal of cleaning water, dirt, and dust.	450,500	SF	\$2/SF	\$901,000
B.	Hand-wash equipment surfaces to < 10 ug/100 cm ² . Includes disposal of cleaning water, dirt, and dust.	200	EA	\$250/EA	\$50,000
C.	Asbestos Removal and Disposal	1	LS	\$100,000	\$100,000
Subtotal Pre-Demolition Cleaning:					\$1,051,000

Table 5
(Cont'd)
Aerovox, Inc. Facility
New Bedford, Massachusetts

Building Demolition Alternative - Option #2

Cost Estimate

Work Activities		Quantity	Units	Unit/Cost	Total
4. Post-Cleaning Verification Sampling					
A.	Post-cleaning verification sampling for building materials	1	LS	\$50,000	\$50,000
B.	Post-cleaning verification sampling for equipment	1	LS	\$45,000	\$45,000
Snbtotal Post-Cleaning Verification Sampling:					\$95,000
5. Utility Modifications and Removal					
A.	Utility modifications, removal, and disposal prior to building demolition.	1	LS	\$100,000	\$100,000
Snbtotal Utility Modifications and Removal:					\$100,000
6. Building Demolition and Disposal					
A.	Removal of wood floor (TSCA material)	235,800	SF	\$5.00/SF	\$1,179,000
B.	Removal of concrete floor above first floor level (TSCA material)	15,000	SF	\$5.50/SF	\$82,500
C.	Removal of concrete floor at first floor level (TSCA material)	96,920	SF	\$4.50/SF	\$436,140
D.	Building demolition	6,703,000	CF	\$0.23/CF	\$1,541,690
E.	Transportation and disposal of demolition debris:				
	- to TSCA landfill (mainly wood and concrete floor materials)	6,360	Ton	\$200/Ton	\$1,272,000
	- to non-TSCA landfill (mainly brick, wood, and drywall)	1,740	Ton	\$50/Ton	\$87,000
	- to steel smelting facility (mainly "I"-beams)	1,225	Ton	\$10/Ton	\$12,250
Subtotal Demolition and Disposal:					\$4,610,580
7. Site Restoration/Asphalt Cap Construction					
A.	Placement and compaction of backfill over concrete floor slab	21,400	CY	\$13.50/CY	\$288,900
B.	40 mil PVC liner	182,133	SF	\$0.34/SF	\$61,925

*Table 5
(Cont'd)
Aerovox, Inc. Facility
New Bedford, Massachusetts*

Building Demolition Alternative - Option #2

Cost Estimate

Work Activities		Quantity	Units	Unit/Cost	Total
C.	Geosynthetic drainage composite	182,133	SF	\$1.40/SF	\$254,986
D.	2" Sand/gravel layer	1,124	CY	\$13.00/CY	\$14,612
E.	6" Run-of-crush stone layer	3,373	CY	\$18.47/CY	\$62,299
F.	2½" Bituminous concrete base course	20,237	SY	\$4.50/SY	\$91,067
G.	1½" Bituminous concrete wearing surface	20,237	SY	\$3.30/SY	\$66,782
Subtotal Site Restoration/Asphalt Cap Construction:					\$840,571
Subtotal Work Activities # 1 through #7:					\$6,724,151
Engineering, Administrative, and Legal Fees (10%):					\$672,415
Contingency (20%):					\$1,344,830
Total Estimated Cost:					\$8,741,396
Rounded To:					\$8,700,000

Notes:

1. Costs are based on contractor estimates from previous projects and BBL's experience.
2. Transportation and disposal costs are based on verbal quotations received in December 1997 from Chemical Waste Management, Inc., and Laidlaw PCB Services.
3. Volume, area, and mass calculations were conducted using the tables and calculations presented in Appendix B.

Assmptions:

The assumptions below are listed in order by each work activity.

- 1A. Sampling and analysis cost estimate includes costs to collect up to 6 discrete full core samples from brick walls in the Pump Room and Tank Room for laboratory analysis for PCBs on a 24-hour turnaround basis.
- 1B. RCRA characterization sampling cost estimate includes costs for up to 20 building material core samples for laboratory analysis for corrosivity, ignitability, reactivity, and Toxicity Characteristic Leaching Procedure (TCLP) volatile organic compounds (VOCs), TCLP semi-volatile organic compounds (SVOCs), and TCLP metals on a 5-day turnaround basis.
- 2A. Conduct equipment/appurtenances inventory cost estimate includes costs for conducting site reconnaissance

*Table 5
(Cont'd)
Aerovox, Inc. Facility
New Bedford, Massachusetts*

Building Demolition Alternative - Option #2

Cost Estimate

activities, reviewing equipment/appurtenances documentation, and meeting with Aerovox facilities personnel to determine equipment/appurtenances (both inside and outside the building) which would be returned to commerce and equipment/appurtenances which would be scrapped.

- 3A. Hand-wash interior surfaces cost estimate includes costs for washing interior horizontal surfaces (including steel beams/columns and HVAC duct work) using detergent and rags to remove visible dust and dirt. Cost includes disposal of cleaning water, rags, dirt, and dust as TSCA waste. Pre-building demolition cleaning area is based on the area of each floor level.
- 3B. Hand-wash equipment cost estimate includes costs for washing equipment using detergent and rags to remove visible dust and dirt. Cost includes disposal of cleaning water, rags, dirt, and dust as TSCA waste.
- 3C. Asbestos removal and disposal cost estimate includes costs for notifications, posting, permitting, air monitoring, recordkeeping, protective equipment, and removal and off-site disposal of the asbestos-containing materials in an approved non-hazardous waste landfill.
- 4A. Post-cleaning verification sampling for building materials cost estimate includes costs to collect verification wipe samples for laboratory analysis to confirm that interior building material surfaces (including steel and duct work) do not contain PCBs at concentrations greater than or equal to 100ug/cm².
- 4B. Post-cleaning verification sampling for equipment cost estimate includes costs to collect verification wipe samples for laboratory analysis to confirm that equipment surfaces do not contain PCBs at concentrations greater than or equal to 10ug/cm².
- 5A. Utility modifications, removal, and disposal cost estimate includes disconnecting electrical services; disconnecting the existing potable water supply; plugging sanitary sewer piping/floor drains; removing electrical equipment, boilers, and compressors; removing light fixtures; removing the fire protection and potable water supply piping; and removing HVAC system components.
- 6A. Removal of wood floor cost estimate includes costs for removing wood floors which contain PCBs at concentrations ≥ 50 ppm. Cost estimate assumes that the wood floors would be removed prior to demolition without affecting the structural integrity of the building.
- 6B. Removal of concrete floor above first floor level cost estimate includes costs for removing the concrete floor (within the second level of the western section of the building) which contains PCBs at concentrations ≥ 50 ppm. Cost estimate assumes that the concrete floor would be removed prior to building demolition without affecting the structural integrity of the building. Cost estimate assumes that the concrete floor slab is 6 inches thick.
- 6C. Removal of concrete floor at first floor level cost estimate includes costs for removing the concrete floor slab from the first floor level of the western section of the building. Cost estimate assumes that the concrete floor slab is 6 inches thick.

*Table 5
(Cont'd)
Aerovox, Inc. Facility
New Bedford, Massachusetts*

Building Demolition Alternative - Option #2

Cost Estimate

- 6D. Building demolition cost estimate includes costs for the demolition of the remaining portion of the building above the floor slab at grade. Demolition would be conducted following wood and concrete floor removal using conventional demolition techniques (i.e., wrecking ball, excavators).
- 6E. Transportation and disposal cost estimate includes costs for transportation and disposal of TSCA and non-TSCA material generated during the demolition activities. Cost estimate assumes that material generated during the wood and concrete floor removal activities (containing PCBs at concentrations ≥ 50 ppm) would be disposed at a TSCA facility. Cost estimate assumes that wood and drywall materials generated under the building demolition cost estimate (excluding steel materials) would be disposed at a non-TSCA landfill. Cost estimate assumes that steel materials will be disposed at a steel smelting facility and that the value of the steel will off-set the smelting costs. Cost estimate for steel to smelting facility only includes costs for transportation.
- 7A. Placement and compaction of backfill cost estimate includes costs for providing, placing, and compacting imported clean backfill material (sand/unwashed gravel) over the removed/remaining first floor concrete floor slab to within one foot of existing grade. Cost estimate assumes that demolition materials, including brick and concrete (excluding wood materials), with PCBs at concentrations < 50 ppm would be mixed with the backfill material and placed over the removed/remaining concrete floor slab.
- 7B-G. Asphalt cap construction cost estimate includes costs for installing a capping system constructed of a 1½ inch thick bituminous concrete wearing surface, a 2½ inch thick bituminous concrete base course, an 8 inch subbase (consisting of 6 inches of run-of-crush stone and 2 inches of sand), a geosynthetic drainage composite, and a 40 mil impermeable PVC or HDPE membrane.

Table 6

Aerovox, Inc. Facility
New Bedford, Massachusetts

Building Demolition Alternative - Option #3

Cost Estimate

- Conduct additional building characterization sampling
- Conduct inventory of equipment/appurtenances
- Clean materials and equipment prior to demolition
- Dispose of materials ≥ 50 ppm PCBs at TSCA landfill
- Disposal of wood materials < 50 ppm PCBs at non-TSCA landfill
- Clean steel to < 100 ug/100 cm² PCBs for disposal at a smelting facility
- Remove the entire first floor concrete slab
- Backfill above the removed concrete floor slab using demolition materials < 50 ppm PCBs and imported clean backfill
- Install asphalt cap over the backfill

	Work Activities	Quantity	Units	Unit/Cost	Total
1. Additional Building Characterization Sampling					
A.	Sampling and analysis of brick walls in Pump Room and Tank Room for PCBs	1	LS	\$2,500	\$2,500
B.	RCRA characterization sampling	1	LS	\$20,000	\$20,000
Subtotal Additional Building Characterization Sampling:					\$22,500
2. Equipment/Appurtenances Inventory					
A.	Conduct equipment/appurtenances inventory. Includes site reconnaissance activities, reviewing documentation for equipment/appurtenances, and meeting with an Aerovox operations personnel.	1	LS	\$4,500	\$4,500
Subtotal Equipment/Appurtenances Inventory:					\$4,500
3. Pre-Demolition Cleaning					
A.	Hand-wash interior surfaces to remove visible dust and dirt and to clean steel surfaces to ≤ 100 ug/100 cm ² . Includes disposal of cleaning water, dirt, and dust.	450,500	SF	\$2/SF	\$901,000
B.	Hand-wash equipment surfaces to < 10 ug/100 cm ² . Includes disposal of cleaning water, dirt, and dust.	200	EA	\$250/EA	\$50,000
C.	Asbestos Removal	1	LS	\$100,000	\$100,000
Subtotal Pre-Demolition Cleaning:					\$1,051,000

Table 6
(Cont'd)
Aerovox, Inc. Facility
New Bedford, Massachusetts

Building Demolition Alternative - Option #3

Cost Estimate

Work Activities		Quantity	Units	Unit/Cost	Total
4. Post-Cleaning Verification Sampling					
A.	Post-cleaning verification sampling for building materials	1	LS	\$50,000	\$50,000
B.	Post-cleaning verification sampling for equipment	1	LS	\$45,000	\$45,000
Subtotal Post-Cleaning Verification Sampling:					\$95,000
5. Utility Modifications and Removal					
A.	Utility modifications, removal, and disposal prior to building demolition.	1	LS	\$100,000	\$100,000
Subtotal Utility Modifications and Removal:					\$100,000
6. Building Demolition and Disposal					
A.	Removal of wood floor (TSCA material)	235,800	SF	\$5.00/SF	\$1,179,000
B.	Removal of concrete floor above first floor level (TSCA material)	15,000	SF	\$5.50/SF	\$82,500
C.	Removal of concrete floor at first floor level (TSCA material)	182,134	SF	\$4.50/SF	\$819,603
D.	Building demolition	6,703,000	CF	\$0.23/CF	\$1,541,690
E.	Transportation and disposal of demolition debris:				
	- to TSCA landfill (mainly wood and concrete floor materials)	10,190	Ton	\$200/Ton	\$2,038,000
	- to non-TSCA landfill (mainly brick, wood, and drywall)	1,740	Ton	\$50/Ton	\$87,000
	- to steel smelting facility (mainly "I"-beams)	1,225	Ton	\$10/Ton	\$12,250
Subtotal Demolition and Disposal:					\$5,760,043

Table 6
(Cont'd)
Aerovox, Inc. Facility
New Bedford, Massachusetts

Building Demolition Alternative - Option #3

Cost Estimate

Work Activities		Quantity	Units	Unit/Cost	Total
7. Site Restoration/Asphalt Cap Construction					
A.	Placement and compaction of backfill material over removed concrete slab area	23,000	CY	\$13.50/CY	\$310,500
B.	40 mil PVC liner	182,133	SF	\$0.34/SF	\$61,925
C.	Geosynthetic drainage composite	182,133	SF	\$1.40/SF	\$254,986
D.	2" Sand/gravel layer	1,124	CY	\$13.00/CY	\$14,612
E.	6" Run-of-crush stone layer	3,373	CY	\$18.47/CY	\$62,299
F.	2½" Bituminous concrete base course	20,237	SY	\$4.50/SY	\$91,067
G.	1½" Bituminous concrete wearing surface	20,237	SY	\$3.30/SY	\$66,782
Subtotal Site Restoration/Asphalt Cap Construction:					\$862,171
Subtotal Work Activities # 1 through #7:					\$7,895,214
Engineering, Administrative, and Legal Fees (10%):					\$789,521
Contingency (20%):					\$1,579,043
Total Estimated Cost:					\$10,263,778
Rounded To:					\$10,300,000

Notes:

1. Costs are based on contractor estimates from previous projects and BBL's experience.
2. Transportation and disposal costs are based on verbal quotations received in December 1997 from Chemical Waste Management, Inc., and Laidlaw PCB Services.
3. Volume, area, and mass calculations were conducted using the tables and calculations presented in Appendix B.

Assumptions:

The assumptions below are listed in order by each work activity.

- 1A. Sampling and analysis cost estimate includes costs to collect up to 6 discrete full core samples from brick walls in the Pump Room and Tank Room for laboratory analysis for PCBs on a 24-hour turnaround basis.

*Table 6
(Cont'd)
Aerovox, Inc. Facility
New Bedford, Massachusetts*

Building Demolition Alternative - Option #3

Cost Estimate

- 1B. RCRA characterization sampling cost estimate includes costs for up to 20 building material core samples for laboratory analysis for corrosivity, ignitability, reactivity, and Toxicity Characteristic Leaching Procedure (TCLP) volatile organic compounds (VOCs), TCLP semi-volatile organic compounds (SVOCs), and TCLP metals on a 5-day turnaround basis.
- 2A. Conduct equipment/appurtenances inventory cost estimate includes costs for conducting site reconnaissance activities, reviewing equipment/appurtenances documentation, and meeting with Aerovox facilities personnel to determine equipment/appurtenances (both inside and outside the building) which would be returned to commerce and equipment/appurtenances which would be scrapped.
- 3A. Hand-wash interior surfaces cost estimate includes costs for washing interior horizontal surfaces (including steel beams/columns and HVAC duct work) using detergent and rags to remove visible dust and dirt. Cost includes disposal of cleaning water, rags, dirt, and dust as TSCA waste. Pre-building demolition cleaning area is based on the area of each floor level.
- 3B. Hand-wash equipment cost estimate includes costs for washing equipment using detergent and rags to remove visible dust and dirt. Cost includes disposal of cleaning water, rags, dirt, and dust as TSCA waste.
- 3C. Asbestos removal and disposal cost estimate includes costs for notifications, posting, permitting, air monitoring, recordkeeping, protective equipment, and removal and off-site disposal of the asbestos-containing materials in an approved non-hazardous waste landfill.
- 4A. Post-cleaning verification sampling for building materials cost estimate includes costs to collect verification wipe samples for laboratory analysis to confirm that interior building material surfaces (including steel and duct work) do not contain PCBs at concentrations greater than or equal to 100ug/cm².
- 4B. Post-cleaning verification sampling for equipment cost estimate includes costs to collect verification wipe samples for laboratory analysis to confirm that equipment surfaces do not contain PCBs at concentrations greater than or equal to 10ug/cm².
- 5A. Utility modifications, removal, and disposal cost estimate includes disconnecting electrical services; disconnecting the existing potable water supply; plugging sanitary sewer piping/floor drains; removing electrical equipment, boilers, and compressors; removing light fixtures; removing the fire protection and potable water supply piping; and removing HVAC system components.
- 6A. Removal of wood floor cost estimate includes costs for removing wood floors which contain PCBs at concentrations ≥ 50 ppm. Cost estimate assumes that the wood floors would be removed prior to demolition without affecting the structural integrity of the building.
- 6B. Removal of concrete floor above first floor level cost estimate includes costs for removing the concrete floor (within the second level of the western section of the building) which contains PCBs at concentrations ≥ 50 ppm. Cost estimate assumes that the concrete floor would be removed prior to building demolition without affecting the structural integrity of the building. Cost estimate assumes that the concrete floor slab is 6 inches thick.

*Table 6
(Cont'd)
Aerovox, Inc. Facility
New Bedford, Massachusetts*


Building Demolition Alternative - Option #3

Cost Estimate


- 6C. Removal of concrete floor at first floor level cost estimate includes costs for removing the concrete floor slab from the entire first floor level of the building. Cost estimate assumes that the concrete floor slab is 6 inches thick.
- 6D. Building demolition cost estimate includes costs for the demolition of the remaining portion of the building above the floor slab at grade. Demolition would be conducted following wood and concrete floor removal using conventional demolition techniques (i.e., wrecking ball, excavators).
- 6E. Transportation and disposal cost estimate includes costs for transportation and disposal of TSCA and non-TSCA material generated during the demolition activities. Cost estimate assumes that material generated during the wood and concrete floor removal activities (containing PCBs at concentrations ≥ 50 ppm) would be disposed at a TSCA facility. Cost estimate assumes that wood and drywall materials generated under the building demolition cost estimate (excluding steel materials) would be disposed at a non-TSCA landfill. Cost estimate assumes that steel materials will be disposed at a steel smelting facility and that the value of the steel will off-set the smelting costs. Cost estimate for steel to smelting facility only includes costs for transportation.
- 7A. Placement and compaction of backfill cost estimate includes costs for providing, placing, and compacting imported clean backfill material (sand/unwashed gravel) over the removed first floor slab area to within one foot of existing grade. Cost estimate assumes that demolition materials, including brick and concrete (excluding wood materials), with PCBs at concentrations < 50 ppm would be mixed with the backfill material and placed over the removed first floor slab area.
- 7B-G. Asphalt cap construction cost estimate includes costs for installing a capping system constructed of a 1½ inch thick bituminous concrete wearing surface, a 2½ inch thick bituminous concrete base course, an 8 inch subbase (consisting of 6 inches of run-of-crush stone and 2 inches of sand), a geosynthetic drainage composite, and a 40 mil impermeable PVC or HDPE membrane.

Figures


BLASLAND, BOUCK & LEE, INC.
engineers & scientists



3RD FLOOR




2ND FLOOR



1ST FLOOR

- LEGEND:
- FLOOR SAMPLE TAKEN BY USEPA ON JUNE 25, 1997
 - ▲ FIELD COMPOSITE (SCRAPE) SAMPLE TAKEN BY BBL ON NOVEMBER 25, 1997
 - DISCRETE CORE SAMPLE TAKEN BY BBL ON NOVEMBER 25, 1997
 - [2.48] TOTAL PCBs < 50 ppm (mg/kg)
 - [128] TOTAL PCBs ≥ 50 ppm (mg/kg)
 - 3-DD-1 SAMPLE I.D. NUMBER



BBL BLASLAND, BOUCK & LEE, INC.
engineers & scientists


Aerovox INC.
740 BELLEVILLE AVE., NEW BEDFORD, MA 02745 USA

INTERPRET DRAWING PER ASME Y14.5M-1994


UNLESS OTHERWISE SPECIFIED	DRAWN BY	DJENKINS	11/18/97
DRAWING IN INCHES	CHECKED BY		
.000 ± .005	APPROVED BY		
.001 ± .01	USED ON	AEROVOX NEW BEDFORD	FULL CORE & DUST & CHIP SCRAPE SAMPLES (USEPA FLOOR CHIP SAMPLES)
FRACTIONS ± 1/64	CAD NO.	0002	SCALE
ANGLES ± 0°30'	SHEET	1 OF 1	

DWG. NO. PAVXX-AG-0002 REV. A


ZONE	LTR	REVISION	BY	DATE	APPR
-	A	ORIGINAL ISSUE	DAJ	11/18/97	



3RD FLOOR




2ND FLOOR



1ST FLOOR

- LEGEND:
- ▲ APPURTENANCE WIPE SAMPLE TAKEN BY USEPA ON JUNE 25, 1997
 - BUILDING MATERIAL WIPE SAMPLE TAKEN BY USEPA ON OCTOBER 7 AND 8, 1997
 - ▲ EQUIPMENT/APURTENANCE WIPE SAMPLE TAKEN BY BBL ON NOVEMBER 24, 1997
 - BUILDING MATERIAL WIPE SAMPLE TAKEN BY BBL ON NOVEMBER 24, 1997
 - 3.3 TOTAL PCBs < 10 ug/100 cm²
 - 18.0 TOTAL PCBs ≥ 10 ug/100 cm²
 - 1-AW-2 SAMPLE I.D. NUMBER




		BLASLAND, BOUCK & LEE, INC. engineers & scientists	FIGURE 2
Aerovox Inc. 740 BELLEVILLE AVE., NEW BEDFORD, MA 02745 USA			
CAD NO. 0002 SCALE N/A SHEET 1 OF 1	DRAWN BY D. JENKINS 11/18/97 CHECKED BY APPROVED BY USED ON AEROVOX NEW BEDFORD	TITLE WIPE SAMPLES DWG. NO. PAVXX-AG-0002 REV. A	UNLESS OTHERWISE SPECIFIED DRAWING IN INCHES .000 ± .005 FRACTIONS ± 1/64 ANGLES ± 0°30'


P:\BBL2\PCP 3/16/98 318-SA-FGL.RCB 03/05/07/AEROVOX/03555M2.DWG

NOTES: THIS DOCUMENT IS THE PROPERTY OF AERVOX AND RETURNABLE UPON REQUEST. IT SHALL NOT BE REPRODUCED OR INFORMATION HEREIN TRANSMITTED IN ANY MANNER WITHOUT WRITTEN CONSENT FROM THE COMPANY. PATENTS HAVE BEEN GRANTED AND PENDING APPLICATIONS ARE PENDING OR IN PROCESS OF PREPARATION ON ALL OF OUR DEVELOPMENTS. 9/28/97

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69



1ST FLOOR



LEGEND

- 043 SOIL SAMPLING LOCATION
- 8-2 SAMPLE DEPTH
- 10.5 TOTAL PCBs < 50 ppm (mg/kg)
- 10.9 TOTAL PCBs > 50 ppm (mg/kg)

NOTES
 1. DRAWING FROM ELECTRONIC FILE FROM AEROVOX, INC.
 DRAWING NO. PAVX-AG-0002 DATED NOVEMBER 18, 1997.
 2. ALL LOCATIONS ARE APPROXIMATE.

X (BET) LAYERS OFF=0. CONCRETE (FLOOR, TIGI), REF. SAMPLE LOCATION, SCRAPES, SEALED AREAS, WIPES, WOOD LOT
 P. AERO.PCB
 3/27/98 DWS4-RCE DWG
 0865001/0865303



Aerovox, INC.
 740 BELLEVILLE AVE., NEW BEDFORD, MA 02745 USA
BUILDING DEMOLITION ALTERNATIVE REPORT


PCB SOIL SAMPLING RESULTS BENEATH CONCRETE SLAB

BBL
 BLASLAND, BOUCK & LEE, INC.
engineers & scientists

FIGURE **3**

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69



LEGEND
 APPROXIMATE EXTENT OF CONCRETE FLOOR SLAB TO BE REMOVED UNDER DEMOLITION OPTION #2

AEROVOX INC.
 740 BELLEVILLE AVE., NEW BEDFORD, MA 02745 USA
 BUILDING DEMOLITION ALTERNATIVE REPORT
APPROXIMATE EXTENT OF CONCRETE FLOOR SLAB TO BE REMOVED UNDER OPTION #2

BBL
 BLASLAND, BOUCK & LEE, INC.
 engineers & scientists
 FIGURE 4

NOTES:
 1. DRAWING FROM ELECTRONIC FILE FROM AEROVOX, INC.
 DRAWING NO. PAVXX-AG-0002 DATED NOVEMBER 18, 1997.
 2. ALL LOCATIONS ARE APPROXIMATE.

X (REF)
 LAYERS: OPT=0;CONCRETE;FLOOR;FIGS;REF;SAMPLE;LOCATIONS;SCRAPES;SEALED;AREAS;WPES;WOOD;OT
 5/26/98 DWG-RCB
 018555004/03835203.DWG

Appendix A ***Analytical Data Report***

BLASLAND, BOUCK & LEE, INC.
engineers & scientists



PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97 Matrix : Wipe
Date Sampled : 24-NOV-97 Method : SW846 8082
Date Extracted: 01-DEC-97 Units : ug

Galson ID: L40282-1 L40282-2 L40282-3
Client ID: 1-FW-1 1-AW-2 1-FW-3

Table with 4 columns: Compound Name, L40282-1, L40282-2, L40282-3. Rows include Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Aroclor-1254, and Aroclor-1260.

Analysis Date 12/02/97 12/02/97 12/03/97
Dilution Factor 1 1 10
Surrogate Recovery 100 % 109 % 0 % D
Control Limits (46-137)

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : 'yo
Date : 12-9-97
NYS DOH # : 11626

Footnotes:
D: Surrogate diluted out.

Printed : 12/03/97 19:31 Report Reference # : 94525





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97
Date Sampled : 24-NOV-97
Date Extracted : 01-DEC-97
Matrix : Wipe
Method : SW846 8082
Units : ug

Galson ID:	L40282-4	L40282-5	L40282-6
Client ID:	1-WW-4	1-FW-5	1-AW-6
Aroclor-1016	<2.5	<2.5	<2.5
Aroclor-1221	<2.5	<2.5	<2.5
Aroclor-1232	<2.5	<2.5	<2.5
Aroclor-1242	<2.5	<2.5	<2.5
Aroclor-1248	7.5	21.	6.4
Aroclor-1254	7.9	38.	4.1
Aroclor-1260	<2.5	<2.5	<2.5
Analysis Date	12/02/97	12/02/97	12/02/97
Dilution Factor	1	1	1
Surrogate Recovery	102 %	93 %	100 %
Control Limits (46-137)			

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : *OK*
Date : 12-~~7~~-97
NYS DOH # : 11626
Footnotes:

D: Surrogate diluted out.

Printed : 12/03/97 19:31

Report Reference # : 94525





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97 Matrix : Wipe
Date Sampled : 24-NOV-97 Method : SW846 8082
Date Extracted: 01-DEC-97 Units : ug

Galson ID: L40282-7 L40282-8 L40282-9
Client ID: 1-AW-7 2-AW-2 2-FW-3

Aroclor-1016	<5	<25	<2.5
Aroclor-1221	<5	<25	<2.5
Aroclor-1232	<5	<25	<2.5
Aroclor-1242	<5	<25	<2.5
Aroclor-1248	47.	150	51.
Aroclor-1254	37.	85.	39.
Aroclor-1260	<5	<25	<2.5
Analysis Date	12/03/97	12/03/97	12/02/97
Dilution Factor	2	10	1
Surrogate Recovery	114 %	0 % D	113 %
Control Limits (46-137)			

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : *SK*
Date : 12-4-97
NYS DOH # : 11626
Footnotes:

D: Surrogate diluted out.

Printed : 12/03/97 19:31

Report Reference # : 94525





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97 Matrix : Wipe
Date Sampled : 24-NOV-97 Method : SW846 8082
Date Extracted: 01-DEC-97 Units : ug

Galson ID: L40282-10 L40282-11 L40282-12
Client ID: 2-FW-4 2-FW-5 2-FW-6

Aroclor-1016	<2.5	<2.5	<2.5
Aroclor-1221	<2.5	<2.5	<2.5
Aroclor-1232	<2.5	<2.5	<2.5
Aroclor-1242	<2.5	<2.5	<2.5
Aroclor-1248	8.3	10.	7.6
Aroclor-1254	9.5	4.8	7.0
Aroclor-1260	<2.5	<2.5	<2.5
Analysis Date	12/02/97	12/03/97	12/02/97
Dilution Factor	1	1	1
Surrogate Recovery	111 %	112 %	111 %
Control Limits (46-137)			

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : *JK*
Date : *12-3-97*
NYS DOH # : 11626
Footnotes:

D: Surrogate diluted out.

Printed : 12/03/97 19:31

Report Reference # : 94525





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97 Matrix : Wipe
Date Sampled : 24-NOV-97 Method : SW846 8082
Date Extracted: 01-DEC-97 Units : ug

Galson ID: L40282-13 L40282-14 L40282-15
Client ID: 2-FW-7 2-AW-1 3-FW-1

Table with 4 columns: Compound Name, L40282-13, L40282-14, L40282-15. Rows include Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Aroclor-1254, Aroclor-1260, Analysis Date, Dilution Factor, Surrogate Recovery, and Control Limits (46-137).

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : [Signature]
Date : 12-3-97
NYS DOH # : 11626
Footnotes:

D: Surrogate diluted out.

Printed : 12/03/97 19:31

Report Reference # : 94525





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97
Date Sampled : 24-NOV-97
Date Extracted: 01-DEC-97
Matrix : Wipe
Method : SW846 8082
Units : ug

Galson ID:	L40282-16	L40282-17	L40282-18
Client ID:	3-FW-2	3-FW-3	3-FW-4
Aroclor-1016	<25	<5	<2.5
Aroclor-1221	<25	<5	<2.5
Aroclor-1232	<25	<5	<2.5
Aroclor-1242	<25	<5	<2.5
Aroclor-1248	100	60.	19.
Aroclor-1254	76.	38.	11.
Aroclor-1260	<25	<5	<2.5
Analysis Date	12/03/97	12/03/97	12/03/97
Dilution Factor	10	2	1
Surrogate Recovery	0 % D	118 %	108 %
Control Limits (46-137)			

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : *JK*
Date : *12-3-97*
NYS DOH # : 11626
Footnotes:

D: Surrogate diluted out.

Printed : 12/03/97 19:31

Report Reference # : 94525





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97 Matrix : Wipe
Date Sampled : 24-NOV-97 Method : SW846 8082
Date Extracted: 01-DEC-97 Units : ug

Table with 4 columns: Galson ID, Client ID, and three sample IDs (L40282-25, L40282-26, L40282-27). Rows include Aroclor-1016 through Aroclor-1260, Analysis Date, Dilution Factor, Surrogate Recovery, and Control Limits.

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : [signature]
Date : 12-3-97
NYS DOH # : 11626
Footnotes:

D: Surrogate diluted out.

Printed : 12/03/97 19:31

Report Reference # : 94525





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97 Matrix : Wipe
Date Sampled : 24-NOV-97 Method : SW846 8082
Date Extracted: 01-DEC-97 Units : ug

Galson ID: L40282-28 L40282-29 L40282-30
Client ID: 3-EW-1 3-EW-2 3-EW-3

Table with 4 columns: Pesticide Name, L40282-28, L40282-29, L40282-30. Rows include Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Aroclor-1254, Aroclor-1260, Analysis Date, Dilution Factor, Surrogate Recovery, and Control Limits.

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : [Signature]
Date : 12-4-97
NYS DOH # : 11626
Footnotes:

D: Surrogate diluted out.

Printed : 12/03/97 19:31

Report Reference # : 94525





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97 Matrix : Wipe
Date Sampled : 24-NOV-97 Method : SW846 8082
Date Extracted: 01-DEC-97 Units : ug

Galson ID: L40282-31 L40282-32 L40282-33
Client ID: 3-EW-4 3-EW-5 1-EW-1

Aroclor-1016	<2.5	<2.5	<2.5
Aroclor-1221	<2.5	<2.5	<2.5
Aroclor-1232	<2.5	<2.5	<2.5
Aroclor-1242	<2.5	<2.5	<2.5
Aroclor-1248	46.	<2.5	38.
Aroclor-1254	22.	<2.5	28.
Aroclor-1260	<2.5	<2.5	<2.5
Analysis Date	12/02/97	12/02/97	12/02/97
Dilution Factor	1	1	1
Surrogate Recovery	97 %	92 %	102 %
Control Limits (46-137)			

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : *SK*
Date : 12-1-97
NYS DOH # : 11626
Footnotes:

D: Surrogate diluted out.

Printed : 12/03/97 19:31

Report Reference # : 94525





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97 Matrix : Wipe
Date Sampled : 24-NOV-97 Method : SW846 8082
Date Extracted: 01-DEC-97 Units : ug

Galson ID:	L40282-34	L40282-35	L40282-36
Client ID:	1-EW-2	1-EW-3	1-EW-4
Aroclor-1016	<50	<2.5	<12
Aroclor-1221	<50	<2.5	<12
Aroclor-1232	<50	<2.5	<12
Aroclor-1242	<50	<2.5	<12
Aroclor-1248	210	7.0	89.
Aroclor-1254	120	6.7	110
Aroclor-1260	<50	<2.5	<12
Analysis Date	12/02/97	12/02/97	12/02/97
Dilution Factor	20	1	5
Surrogate Recovery	0 % D	99 %	100 %
Control Limits (46-137)			

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : *JK*
Date : 12-4-97
NYS DOH # : 11626
Footnotes:

D: Surrogate diluted out.

Printed : 12/03/97 19:31

Report Reference # : 94525





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97
Date Sampled : 24-NOV-97
Date Extracted: 01-DEC-97
Matrix : Wipe
Method : SW846 8082
Units : ug

Galson ID: Q-5147 Q-5148
Client ID: PBLK 5147 PBLK 5148

Aroclor-1016	<2.5	<2.5
Aroclor-1221	<2.5	<2.5
Aroclor-1232	<2.5	<2.5
Aroclor-1242	<2.5	<2.5
Aroclor-1248	<2.5	<2.5
Aroclor-1254	<2.5	<2.5
Aroclor-1260	<2.5	<2.5
Analysis Date	12/02/97	12/02/97
Dilution Factor	1	1
Surrogate Recovery	112 %	113 %
Control Limits (46-137)		

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : *JK*
Date : 12-4-97
NYS DOH # : 11626
Footnotes:

D: Surrogate diluted out.





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97 Matrix : Bulk
Date Sampled : 24-NOV-97 Method : SW846-8082
Date Extracted: 28-NOV-97 Units : mg/Kg

Galson ID: L40282-19 L40282-20 L40282-21
Client ID: 2-FC-1 2-FC-2 2-FC-3

Table with 4 columns: Pesticide Name, L40282-19, L40282-20, L40282-21. Rows include Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Aroclor-1254, Aroclor-1260, Analysis Date, Dilution Factor, Surrogate Recovery, and Control Limits (60-150).

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : [Signature]
Date : 12-4-97
NYS DOH # : 11626
Footnotes:

Results are reported on a dry weight basis.
See enclosed sheet for percent moisture values.
D: Surrogate diluted out.

Printed : 12/03/97 19:32

Report Reference # : 94538





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97 Matrix : Bulk
Date Sampled : 24-NOV-97 Method : SW846-8082
Date Extracted: 28-NOV-97 Units : mg/Kg

Galson ID: L40282-22 L40282-23 L40282-24
Client ID: 2-FC-4 2-FC-5 2-FC-6

Aroclor-1016	<7.1	<4000	<1.7
Aroclor-1221	<7.1	<4000	<1.7
Aroclor-1232	<7.1	<4000	<1.7
Aroclor-1242	<7.1	56000	<1.7
Aroclor-1248	91.	<4000	18.
Aroclor-1254	54.	<4000	10.
Aroclor-1260	<7.1	<4000	<1.7
Analysis Date	12/03/97	12/03/97	12/03/97
Dilution Factor	200	100000	50
Surrogate Recovery	0 % D	0 % D	0 % D
Control Limits (60-150)			

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : *OK*
Date : 12-4-97
NYS DOH # : 11626
Footnotes:

Results are reported on a dry weight basis.
See enclosed sheet for percent moisture values.
D: Surrogate diluted out.

Printed : 12/03/97 19:32

Report Reference # : 94538





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97
Date Sampled : 24-NOV-97
Date Extracted : 28-NOV-97
Matrix : Bulk
Method : SW846-8082
Units : mg/Kg

Galson ID:	L40282-37	L40282-38	L40282-39
Client ID:	3-FC-1	3-WC-1	3-FC-2

Aroclor-1016	<7.2	<0.17	<36
Aroclor-1221	<7.2	<0.17	<36
Aroclor-1232	<7.2	<0.17	<36
Aroclor-1242	<7.2	<0.17	<36
Aroclor-1248	58.	1.5	140
Aroclor-1254	28.	0.98	64.
Aroclor-1260	<7.2	<0.17	<36
Analysis Date	12/03/97	12/02/97	12/02/97
Dilution Factor	200	10	1000
Surrogate Recovery	0 % D	0 % D	0 % D
Control Limits (60-150)			

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : 80
Date : 12-4-97
NYS DOH # : 11626
Footnotes:

Results are reported on a dry weight basis.
See enclosed sheet for percent moisture values.
D: Surrogate diluted out.

Printed : 12/03/97 19:32

Report Reference # : 94538





BASLAND, BOUCK & LEE, INC.
engineers & scientists
6723 Towpath Road, P.O. Box 66
Syracuse, New York 13214-0066
TEL: (315) 446-9120

1074

CHAIN OF CUSTODY RECORD

PROJ. NO. 07.001.01	PROJECT NAME AEROVOX SAMPLING PROGRAM	STATION LOCATION		
		DATE	TIME	GRAB
SAMPLERS: (Signature) <i>[Signature]</i>		Blasland, Bouck & Lee 1-FW-1		
1/24/97 16:00	1-FW-1	X		
1/24/97 16:05	1-AW-2	X		
1/24/97 16:10	1-FW-3	X		
1/24/97 16:15	1-WW-4	X		
1/24/97 16:20	1-FW-5	X		
1/24/97 16:25	1-AW-6	X		
1/24/97 16:30	1-AW-7	X		
1/24/97 17:05	2-AW-2	X		
1/24/97 17:30	2-FW-3	X		
1/24/97 17:40	2-FW-4	X		
1/24/97 17:50	2-FW-5	X		
1/24/97 17:55	2-FW-6	X		
1/24/97 18:05	2-FW-7	X		
1/24/97 18:35	2-AW-1	X		

RELINQUISHED BY (Signature)	DATE	TIME	RECEIVED BY (Signature)	DATE	TIME
<i>[Signature]</i>	1/24/97	16:00	<i>[Signature]</i>	1/26/97	10:20
<i>[Signature]</i>					
<i>[Signature]</i>					

DATE	TIME	RECEIVED FOR LABORATORY BY (Signature)	DATE	TIME
		<i>[Signature]</i>	11-26-97	10:20

Remarks: *over temp 56°C TS 10*

Remarks: *SENT TO GALSON LABORATORYS
FED EX # 609 468 8491*

CHAIN OF CUSTODY RECORD

PROJ. NO.		PROJECT NAME		STATION LOCATION		REMARKS		
977, 00, 01		AEROLUX SAMPLING PROGRAM						
SAMPLERS: (Signature)				PCBS				
STA. NO.	DATE	TIME	COMP	GRAB	DATE	TIME	REMARKS	
	11/24/97	18:20		X	3-FW-1		L40282-15 <u>ASAP TURNAROUND</u>	
	11/24/97	18:30		X	3-FW-2		L40282-16	
	11/24/97	18:40		X	3-FW-3		L40282-17	
	11/24/97	18:50		X	3-FW-4		L40282-18	
	11/24/97	19:00		X	2-FC-1		L40282-19 ^{PF} 56 <u>SETS</u> (TC)	
	11/24/97	19:10		X	2-FC-2		L40282-20 <u>26 Imp</u>	
	11/24/97	19:20		X	2-FC-3		L40282-21	
	11/24/97	19:30		X	2-FC-4		L40282-22	
	11/24/97	19:40		X	2-FC-5		L40282-23	
	11/24/97	19:50		X	2-FC-6		L40282-24	
	11/24/97	20:00		X	2-EW-1		L40282-25	
	11/24/97	20:10		X	2-EW-2		L40282-26	
	11/24/97	20:20		X	2-EW-3		L40282-27	
	11/24/97	20:30		X	3-EW-1		L40282-28	
Relinquished by: (Signature)				DATE	TIME	Relinquished by: (Signature)	DATE	TIME
[Signature]				11/24/97	1600	[Signature]		
Relinquished by: (Signature)				DATE	TIME	Relinquished by: (Signature)	DATE	TIME
[Signature]						[Signature]		
Relinquished by: (Signature)				DATE	TIME	Relinquished by: (Signature)	DATE	TIME
[Signature]				11-24-97	1030	[Signature]	11-24-97	1030
Remarks: TO GILSON LABORATORY SENT TO GILSON LABORATORY FED EX # 609 468 0491								

Distribution: Original Accompanies Shipment; Copy to Coordinator Field Files



PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97 Matrix : Bulk
Date Sampled : 25-NOV-97 Method : SW846-8082
Date Extracted: 28-NOV-97 Units : mg/Kg

Galson ID: L40298-9 L40298-10 L40298-11
Client ID: 1-DD-3 1-DD-4 1-DD-5

Table with 4 columns: Compound Name, L40298-9, L40298-10, L40298-11. Rows include Aroclor-1016, Aroclor-1221, Aroclor-1232, Aroclor-1242, Aroclor-1248, Aroclor-1254, Aroclor-1260, Analysis Date, Dilution Factor, Surrogate Recovery, and Control Limits (60-150).

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : [Signature]
Date : 12-3-97
NYS DOH # : 11626
Footnotes:

Results are reported on a dry weight basis.
See enclosed sheet for percent moisture values.
D: Surrogate diluted out.

Printed : 12/03/97 16:25

Report Reference # : 94534





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : Aerovox Sampling Program

Date Received : 26-NOV-97
Date Sampled : 25-NOV-97
Date Extracted : 28-NOV-97
Matrix : Bulk
Method : SW846-8082
Units : mg/Kg

Galson ID: L40298-12 Q-5146
Client ID: 1-DD-6 PBLK 5146

Aroclor-1016	<34	<0.02
Aroclor-1221	<34	<0.02
Aroclor-1232	<34	<0.02
Aroclor-1242	<34	<0.02
Aroclor-1248	180	<0.02
Aroclor-1254	88.	<0.02
Aroclor-1260	<34	<0.02

Analysis Date	12/03/97	12/03/97
Dilution Factor	2000	1
Surrogate Recovery	0 % D	89 %
Control Limits (60-150)		

Approved by : Oommen Kappil
Date : 03-DEC-97
QC by : *JK*
Date : 12-3-97
NYS DOH # : 11626
Footnotes:

Results are reported on a dry weight basis.
See enclosed sheet for percent moisture values.
D: Surrogate diluted out.

Printed : 12/03/97 16:25

Report Reference # : 94534





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : AEROVOX

Date Received : 13-FEB-98 Matrix : Soil
Date Sampled : 11-FEB-98 - 12-FEB-98 Method : SW846 8082
Date Extracted : 14-FEB-98 Units : ug/Kg

Table with 4 columns: Galson ID, Client ID, and three columns of analytical data (L41423-7, L41423-8, L41423-9). Rows include Aroclor-1016 through Aroclor-1260, Percent Moisture (%), Analysis Date, Dilution Factor, Surrogate Recovery, and Control Limits (57-150).

Approved by : Gommen Kappil
Date : 17-FEB-98
QC by : [Signature]
Date : 2/23/98
NYS DOH # : 11626
Footnotes:

D: Surrogate diluted out.
Results are reported on a dry weight basis.

Printed : 02/23/98 10:47

Report Reference # : 97824





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
 Account # : 10624
 Site : AEROVOX

Date Received : 13-FEB-98
 Date Sampled : 11-FEB-98 - 12-FEB-98
 Date Extracted: 14-FEB-98

Matrix : Soil
 Method : SW846 8082
 Units : ug/Kg

Galson ID: Client ID:	L41423-11 1B6 (0-2)	L41423-13 1B10 (0-2)	L41423-15 1B8 (0-2)
Aroclor-1016	<1800000	<1800	<190000
Aroclor-1221	<1800000	<1800	<190000
Aroclor-1232	<1800000	<1800	<190000
Aroclor-1242	<1800000	<1800	<190000
Aroclor-1248	<1800000	6700	<190000
Aroclor-1254	1800000	5100	1800000
Aroclor-1260	<1800000	<1800	<190000
Percent Moisture (%)	7	7	18
Analysis Date	02/17/98	02/20/98	02/17/98
Dilution Factor	100000	100	10000
Surrogate Recovery	0 % D	0 % D	0 % D
Control Limits (57-150)			

Approved by : Connen Kappil
 Date : 17-FEB-98
 QC by : *[Signature]*
 Date : *[Signature]*
 NYS DOH # : 11626
 Footnotes:

D: Surrogate diluted out.
 Results are reported on a dry weight basis.

Printed : 02/23/98 10:47

Report Reference # : 97824





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
 Account # : 10624
 Site : AEROVOX

Date Received : 13-FEB-98 Matrix : Soil
 Date Sampled : 11-FEB-98 - 12-FEB-98 Method : SW846 8082
 Date Extracted: 14-FEB-98 Units : ug/Kg

Galson ID:	L41423-17	L41423-19	L41423-21
Client ID:	1H6 (0-2)	1F7 (0-2)	1F10 (0-2)

Aroclor-1016	<180	<1800	<1700
Aroclor-1221	<180	<1800	<1700
Aroclor-1232	<180	<1800	<1700
Aroclor-1242	<180	<1800	<1700
Aroclor-1248	1500	6800	8600
Aroclor-1254	800	6200	3800
Aroclor-1260	<180	<1800	<1700
Percent Moisture (%)	11	7	4
Analysis Date	02/20/98	02/20/98	02/20/98
Dilution Factor	10	100	100
Surrogate Recovery	0 % D	0 % D	0 % D
Control Limits (57-150)			

Approved by : Connen Kappil
 Date : 17-FEB-98
 QC by : *[Signature]*
 Date : *[Signature]*
 NYS DOH # : 11626
 Footnotes:

D: Surrogate diluted out.
 Results are reported on a dry weight basis.

Printed : 02/23/98 10:47

Report Reference # : 97824





PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
 Account # : 10624
 Site : AEROVOX

Date Received : 13-FEB-98
 Date Sampled : 11-FEB-98 - 12-FEB-98
 Date Extracted: 14-FEB-98

Matrix : Soil
 Method : SW846 8082
 Units : ug/Kg

Galson ID:	L41423-23	L41423-25	L41423-27
Client ID:	1B20 (0-2)	1B35 (0-2)	1C52 (0-2)
Aroclor-1016	<170	<1800	<16
Aroclor-1221	<170	<1800	<16
Aroclor-1232	<170	<1800	<16
Aroclor-1242	<170	<1800	<16
Aroclor-1248	400	14000	140
Aroclor-1254	540	5600	78.
Aroclor-1260	<170	<1800	<16
Percent Moisture (%)	7	10	0
Analysis Date	02/20/98	02/20/98	02/23/98
Dilution Factor	10	100	1
Surrogate Recovery	0 % D	0 % D	59 %
Control Limits (57-150)			

Approved by : Conmen Kappil
 Date : 17 FEB-98
 QC by : *[Signature]*
 Date : *2/23/98*
 NYS DOH # : 11626
 Footnotes:

D: Surrogate diluted out.
 Results are reported on a dry weight basis.

Printed : 02/23/98 10:47

Report Reference # : 97824





Galson
Laboratories

PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : AEROVOX

Date Received : 13-FEB-98
Date Sampled : 11-FEB-98 - 12-FEB-98
Date Extracted : 14-FEB-98

Matrix : Soil
Method : SW846 8082
Units : ug/Kg

Galson ID:	L41423-29	L41423-32	Q-5299
Client ID:	1E38 (0-2)	AV-DUP-1	PBLK 5299
Aroclor-1016	<170	<1700	<17
Aroclor-1221	<170	<1700	<17
Aroclor-1232	<170	<1700	<17
Aroclor-1242	<170	<1700	<17
Aroclor-1248	320	8600	<17
Aroclor-1254	300	3900	<17
Aroclor-1260	<170	<1700	<17
Percent Moisture (%)	6	5	NA
Analysis Date	02/20/98	02/20/98	02/16/98
Dilution Factor	10	100	1
Surrogate Recovery	0 % D	0 % D	82 %
Control Limits (57-150)			

Approved by : Oommen Kappil
Date : 17 FEB-98
QC by : *[Signature]*
Date : 5/23/98
NYS DOH # : 11626
Footnotes:

D: Surrogate diluted out.
Results are reported on a dry weight basis.

Printed : 02/23/98 10:47

Report Reference # : 97824



PESTICIDE ANALYTICAL REPORT



Client : Blasland, Bouck & Lee
Account # : 10624
Site : AEROVOX

Date Received : 13-FEB-98 Matrix : Soil
Date Sampled : 11-FEB-98 - 12-FEB-98 Method : SW846 8082
Date Extracted: 14-FEB-98 Units : ug/Kg

Galson ID: L41423-1 L41423-3 L41423-5
Client ID: 1D63 (0-2) 1E59 (0-2) 1C5 (0-2)

Table with 4 columns: Analyte, L41423-1, L41423-3, L41423-5. Rows include Aroclor-1016 through Aroclor-1260, Percent Moisture (%), Analysis Date, Dilution Factor, Surrogate Recovery, and Control Limits (57-150).

Approved by : Gommen Kappil
Date : 17-FEB-98
QC by : [Signature]
Date : 2/23/98
NYS DOH # : 11626
Footnotes:

D: Surrogate diluted out.
Results are reported on a dry weight basis.

Printed : 02/23/98 10:47

Report Reference # : 97824





BBL
 BASAND, BOGGS & LEBLANC
 engineers & scientists
 6723 Tawpath Road, P.O. Box 66
 Syracuse, New York 13214-0066
 TEL: (315) 446-9120

***** Contact Dave Dims of BBL for ~~Hold~~ possible analysis, and for Sample Results
 Need Results by Tuesday 2/17/98

CHAIN OF CUSTODY RECORD

PROJECT NO.	PROJECT NAME	CUSTODY TAPE NUMBER	DATE	TIME	COMP.	GRAB	SAMPLE TYPE			Containers	REMARKS		
							SOLID	WIPE	WATER				
03855601	AEROVOX SOIL SAMPLING												
	BELOW CONCRETE FLOOR												
ID63	(0-2")	2/17/98	1717		X	X			1	X	315-446-9120		
ID63	(2-6")		1717		X	X			1	X	* Hold / Forward analysis		
IE54	(0-2")		1803		X	X			1	X			
IE59	(2-6")		1803		X	X			1	X	* Hold		
IC5	(0-2")		1852		X	X			1	X			
IC5	(2-6")		1852		X	X			1	X	* Hold		
ID7	(0-2")		1946		X	X			1	X	* Hold / MS/MSD		
ID7	(2-6")		1946		X	X			1	X	* Hold		
IB6	(0-2")		2015		X	X			1	X			
IB6	(2-6")		2015		X	X			1	X	* Hold		
IB6	(0-2")		2045		X	X			1	X			
IB6	(2-6")		2045		X	X			1	X	* Hold		
IB8	(0-2")		2128		X	X			1	X			
IB8	(2-6")		2128		X	X			1	X	* Hold		
Relinquished by: (Signature)			DATE	TIME	Received by: (Signature)			Relinquished by: (Signature)			DATE	TIME	Relinquished by: (Signature)
[Signature]			2/17/98	1800	[Signature]			[Signature]					
Relinquished by: (Signature)			DATE	TIME	Received by: (Signature)			Relinquished by: (Signature)			DATE	TIME	Relinquished by: (Signature)
[Signature]					[Signature]			[Signature]					
Relinquished by: (Signature)			DATE	TIME	Received for Laboratory by: (Signature)			DATE	TIME	Remarks:	DATE	TIME	
[Signature]					[Signature]			2-13-98	1020	SENT TO GALESON	2-13-98	1020	FED EX # 881952476256



BBL
 BLASAND, BOUCK & LEE, INC.
 engineers & scientists
 6723 Towpath Road, P.O. Box 66
 Syracuse, New York 13214-0066
 TEL: (315) 446-9120

CHAIN OF CUSTODY RECORD

PROJECT NO.	PROJECT NAME	CUSTODY TAPE NUMBER	DATE	TIME	COMP.	GRAB	SAMPLE TYPE			Containers	REMARKS	
							SOLID	WIPE	WATER			
D38.55	AEROBOX SOIL SAMPLING BELOW CONCRETE FLOOR											
I H 6	(0-2")	2/11/94	2211		X	X			1	X		
I H 6	(2-6")		2311		X	X			1	X	* Hold	
I F 7	(0-2")		2305		X	X			1	X		
I F 7	(2-6")		2305		X	X			1	X	* Hold	
I F 10	(0-2")	4/2/94	0043		X	X			1	X		
I F 10	(2-6")		0043		X	X			1	X	* Hold	
I B 20	(0-2")		828		X	X			1	X		
I B 20	(2-6")		828		X	X			1	X	* Hold	
I B 35	(0-2")		0939		X	X			1	X		
I B 35	(2-6")		0939		X	X			1	X	* Hold	
I C 52	(0-2")		1018		X	X			1	X		
I C 52	(2-6")		1018		X	X			1	X	* Hold	
I E 38	(0-2")		1100		X	X			1	X		
I E 38	(2-6")		1100		X	X			1	X	* Hold	
Relinquished by: (Signature)		DATE		TIME	Received by: (Signature)			Relinquished by: (Signature)			DATE	TIME
[Signature]		2/12/94		1800	[Signature]			[Signature]			2-13-96	1020
Relinquished by: (Signature)		DATE		TIME	Received by: (Signature)			Relinquished by: (Signature)			DATE	TIME
[Signature]					[Signature]			[Signature]			2-13-96	1020
Relinquished by: (Signature)		DATE		TIME	Received for Laboratory by: (Signature)			DATE			TIME	REMARKS
[Signature]					[Signature]			2-13-96			1020	SENT TO GALSON FFD EX 4 881952470256



6723 Towpath Road, P.O. Box 66
 Syracuse, New York 13214-0066
 TEL: (315) 446-9120

CHAIN OF CUSTODY RECORD

PROJECT NO.	PROJECT NAME	AEROLIX SOIL SAMPLING			DATE	TIME	COMP.	GRAB	SAMPLE TYPE			REMARKS
		LAB ID	CUSTODY TAPE NUMBER	BELOW CONCRETE FLOOR					SOLID	WIPE	WATER	
038-55.011		AV-RB-1	7/12/99	1130			X		X		1	
		AV-DIG-1	7/12/99	-			X	X			1	
Relinquished by: (Signature)	TOTAL	DATE	7/12/99	TIME	1130	Received by: (Signature)	DATE	2-13-98	TIME	1020	Relinquished by: (Signature)	REMARKS: SENT TO
Relinquished by: (Signature)		DATE		TIME		Received by: (Signature)	DATE		TIME		Relinquished by: (Signature)	
Relinquished by: (Signature)		DATE		TIME		Received for Laboratory by: (Signature)	DATE		TIME		Relinquished by: (Signature)	



PESTICIDE ANALYTICAL REPORT

Client : Blasland, Bouck & Lee
Account # : 10624
Site : AEROVOX

Date Received : 13-FEB-98
Date Sampled : 11-FEB-98
Date Extracted: 19-FEB-98

Matrix : Soil
Method : SW846 8082
Units : ug/Kg

Galson ID: L41468-1 L41468-2 Q-5309
Client ID: 1D7 2-6 1B6 2-6 PBLK 5309

Table with 4 columns: Analyte, L41468-1, L41468-2, Q-5309. Rows include Aroclor-1016 through Aroclor-1260, Percent Moisture (%), Analysis Date, Dilution Factor, Surrogate Recovery, and Control Limits (57-150).

Approved by : Oommen Kappil
Date : 20-FEB-98
QC by [Signature]
Date [Signature]
NYS DOH # : 11626
Footnotes:

D: Surrogate diluted out.
Results are reported on a dry weight basis.

Printed : 02/20/98 09:42

Report Reference # : 98011



(*) Contact Dave Ulin of BBL for *** Hold** for possible analysis, and for Sample Results
(*) - Need Results by Tuesday 2/17/98

CHAIN OF CUSTODY RECORD

PROJECT NO.	PROJECT NAME	AEROVOX SOIL SAMPLING				DATE	TIME	COMP.	GRAB	SAMPLE TYPE			Number of Containers	REMARKS
		CUSTODY TAPE NUMBER IN	DATE	TIME	SOLID					WIPE	WATER			
038.55.001	BELOW CONCRETE FLOOR													
1D63	(0-2")	2/14/98	1717		X	X						1	X	
1D63	(2"-6")		1717		X	X						1	X	* Hold, Do not analyze
1E59	(0-2")		1803		X	X						1	X	
1E59	(2"-6")		1803		X	X						1	X	* Hold
1C5	(0-2")		1852		X	X						1	X	* Hold
1C5	(2"-6")		1852		X	X						1	X	* Hold
1D7	(0-2")		1946		X	X						1	X	* Hold
1D7	(2"-6")		1946		X	X						1	X	* Hold
1B6	(0-2")		2015		X	X						1	X	* Hold
1B6	(2"-6")		2015		X	X						1	X	* Hold
1B10	(0-2")		2045		X	X						1	X	* Hold
1B10	(2"-6")		2045		X	X						1	X	* Hold
1B8	(0-2")		2128		X	X						1	X	* Hold
1B8	(2"-6")		2128		X	X						1	X	* Hold
Relinquished by: (Signature)		DATE		TIME	Received by: (Signature)			DATE			TIME	Relinquished by: (Signature)		
<i>John P. Menard</i>		2/12/98		1800										
Relinquished by: (Signature)		DATE		TIME	Received by: (Signature)			DATE			TIME	Relinquished by: (Signature)		
Relinquished by: (Signature)		DATE		TIME	Received for Laboratory by: (Signature)			DATE			TIME	Remarks:		
					<i>[Signature]</i>			2-13-98			1020	SENT TO GALSON FED EX # 801952476256		

1073

Appendix B
Building Material Volume
and Mass Calculations

BLASLAND, BOUCK & LEE, INC.
engineers & scientists

Appendix B

**Aerovox, Inc. Facility
New Bedford, Massachusetts**

Building Material Volume and Mass Calculations

The calculations presented in Table B were performed in order to estimate the mass and volume of materials which would be generated during the demolition activities of the Aerovox, Inc. (Aerovox) facility, located in New Bedford, Massachusetts. These calculations are approximate and are intended for the purpose of estimating the cost of remedial measures which can be applied to address the presence of polychlorinated biphenyls (PCBs) at the Aerovox facility. It should be noted that calculations are based on the average densities of select solids⁽¹⁾, and no voids (empty spaces) were assumed in the materials. Therefore, the actual volume of the materials to be generated during the demolition activities will increase from those presented in Table B. As such, a volume bulking factor of 1.5 has been applied to volumes presented in tables B1 and B2 for wood material in order to better estimate transportation and disposal costs. A description and explanation of the terms used in Table B is presented below.

Basic Units:

For ease of calculation and manipulation of volume/mass estimates, "basic units" were created. A "basic unit" is specified in the column labeled "Unit", and may be a linear foot (lin ft) of the structure, such as wall, steel beam, etc., a square foot (sq ft) of a structure, such as wall, floor, etc., or individual "unit" (each), such as window, wooden column, etc. Based on the average densities and known dimensions of the "basic unit", the volume (Volume per Unit) and mass (Mass per Unit) of the "basic unit" were calculated. In cases, where "basic unit" consisted of material with the same average density, but the size of the "basic unit" varies (for example 4" thick and 5" thick brick wall), the appropriate dimensions were listed in column labeled "Size".

Volume/Mass Calculations:

The facility was divided into Eastern Section and Western Section, and then each section was divided by floors (levels). This layout provides a mechanism to determine the volume/mass of the separate sections of the building, as needed.

In order to determine the volume/mass of the structure(s) (such as brick wall), the number of the "basic units" (sq ft) of which the structure(s) consist was determined, and then multiplied by the "Volume per Unit" and "Mass per Unit", respectively. The results of the mass and volume calculations created the basis for demolition/cleanup cost presented in Table 3, 4, and 5 of this document.

Assumptions:

1. ⁽¹⁾ - Average densities of the select materials based on data presented in "Handbook of Chemistry and Physics", 76th Edition, 1996.
2. Each level's volume and mass do not include the ceiling (except for the roof of the building). The volume/mass of each ceiling is calculated as the floor of the next higher level.

Table B-1 - cont.

Aerovox, Inc. Facility

Building Material Volume and Mass Calculations

Eastern Section

Basic Units:

1st Floor

2nd Floor

3rd Floor

Structure	Size	Volume Per Unit [cf]	Mass Per Unit [lb]	Unit	1st Floor			2nd Floor			3rd Floor			
					No. of Units	Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]	
Base Wall:	1" thick	3	540	lin. ft.	1425	4275	769500	0	0	0	0	0	0	0
Concrete Floor:	6" thick	0.5	90	sq. ft.	85214	42607	7669260	0	0	0	0	0	0	0
Brick Walls:	12" thick	1	112	sq. ft.	2246	2246	251552	2325	2325	260400	3525	3525	394800	
	16" thick	1.333	150	sq. ft.	4194	5590.602	629100	7650	10197.45	1147500	8116	10818.63	1217400	
Wooden Walls/Floor:	4" thick	0.333	9	sq. ft.	3564	1186.812	32076	0	0	0	0	0	0	
	5" thick	0.416	11.25	sq. ft.	0	0	0	86182	35851.71	969547.5	86182	35851.71	969547.5	
Drywall:	9' high	0.91	36.5	lin. ft.	0	0	0	0	0	0	0	0	0	
	10' high	1.01	40.5	lin. ft.	0	0	0	0	0	0	0	0	0	
	12' high	1.22	48.7	lin. ft.	0	0	0	0	0	0	0	0	0	
Particle Board Wall:	10' high	1.01	36.4	lin. ft.	3100	3782	135408	2365	2388.65	86086	2320	2343.2	84448	
	12' high	1.22	43.68	lin. ft.	0	0	0	0	0	0	0	0	0	
	16' high	1.62	58.24	lin. ft.	0	0	0	0	0	0	0	0	0	
Wooden Columns	9" high	3.14	138	each	0	0	0	0	0	0	0	0	0	
	10" high	3.5	154	each	0	0	0	0	0	0	0	0	0	
	12" high	4.18	184	each	220	919.6	40480	0	0	0	0	0	0	
	16" high	5.6	246	each	0	0	0	220	1232	54120	0	0	0	
	17" high	5.95	261.8	each	0	0	0	0	0	0	220	1309	57596	
Steel Beams:	W21 x 62	0.127	62	lin. ft.	7535	956.945	467170	7535	956.945	467170	7535	956.945	467170	
Steel Plate:	0.5" thick	0.04	19.48	sq. ft.	0	0	0	4728	189.12	92101.44	0	0	0	
Windows:	1" plyw'd	8.91	338	each	0	0	0	0	0	0	0	0	0	
	1/64" met	0.14	68	each	0	0	0	0	0	0	0	0	0	
8' X 13'	9.05	406	each	56	506.8	22736	119	1076.95	48314	119	1076.95	48314		
Total square feet/pounds:					62070.76	1E+07	54217.83	3125239	55881.44	3239276	55881.44	3239276		
Total cubic yards:					2299.101	cu. yds.	2008.228	cu. yds.	2069.848	cu. yds.	2069.848	cu. yds.		
Total Tons:					5008.641	Tons	1562.619	Tons	1619.638	Tons	1619.638	Tons		
Roof - Eastern Section:					1474	cubic yards	14771.81	cubic yards	17667.55	Tons	17667.55	Tons		
TOTAL BUILDING MATERIAL VOLUME:					1474	cubic yards	14771.81	cubic yards	17667.55	Tons	17667.55	Tons		
TOTAL BUILDING MATERIAL MASS:					517	Tons	17667.55	Tons	17667.55	Tons	17667.55	Tons		

Table B-2

Aerovox, inc. Facility

Materials to TSCA Landfill Under Option #1 (Excluding Concrete Floor at Grade)

Structure	Size	Volume		Unit	No. of Units	Mass		Western Section:		
		[cf]	[lb]			1st Floor	2nd Floor			
		Per Unit	Per Unit			Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]
Base Concrete Wall:	1' thick	3	540	lin. ft.		0	0		0	0
Concrete Floor:	6" thick	0.5	90	sq. ft.		0	0	15000	7500	1350000
Brick Walls:	12" thick	1	112	sq. ft.		0	0		0	0
	16" thick	1.333	150	sq. ft.		0	0		0	0
Wooden Walls/Floor:	4" thick	0.333	9	sq. ft.	3186	1060.938	28674			
	5" thick	0.416	11.25	sq. ft.		0	0	56650	23566.4	637312.5
Drywall:	9' high	0.91	36.5	lin. ft.		0	0		0	0
2"X4" stud every 2'	10' high	1.01	40.5	lin. ft.		0	0		0	0
	12' hi h	1.22	48.7	lin. ft.		0	0		0	0
Wooden Columns	9' high	3.14	138	each		0	0		0	0
8" diameter	10' high	3.5	154	each		0	0		0	0
	12" high	4.18	184	each		0	0		0	0
	16' high	5.6	246	each		0	0		0	0
Steel Beams:	W21 x 62	0.127	62	lin. ft.		0	0		0	0
Steel Plate	0.5" thick	0.04	19.48	sq. ft.		0	0		0	0
Windows:	1" plyw'd	5.83	221	each		0	0		0	0
6' X 11'	1/64" met	0.09	44.7	each		0	0		0	0
		5.92	265.7	each		0	0		0	0
Total square feet/pounds:						1060.938	28674		31066.4	1987313
Total cubic yards:						39.29714	cu. yds.		1150.699	cu. yds.
Total Tons:						14.337	Tons		993.6563	Tons

Table B-2 - cont.

Aerovox, Inc. Facility

Materials to TSCA Landfill Under Option #1 (Excluding Concrete Floor at Grade)

Eastern Section

Structure	Size	Volume		Unit	1st Floor		2nd Floor		3rd Floor	
		Per Unit [cf]	Mass [lb]		No. of Units	Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]
Base Wall:	1' thick	3	540	lin. ft.	0	0	0	0	0	0
Brick Walls:	12" thick	1	112	sq. ft.	0	0	0	0	0	0
	16" thick	1.333	150	sq. ft.	0	0	0	0	0	0
					0	0	0	0	0	0
Wooden Walls/Floor:	4" thick	0.333	9	sq. ft.	3564	1186.812	32076	0	0	0
	5" thick	0.416	11.25	sq. ft.	0	0	0	86182	35851.71	969547.5
Drywall:	9' high	0.91	36.5	lin. ft.	0	0	0	0	0	0
	10' high	1.01	40.5	lin. ft.	0	0	0	0	0	0
	12' hi h	1.22	48.7	lin. ft.	0	0	0	0	0	0
Particle Board Wall:	10' high	1.01	36.4	lin. ft.	0	0	0	0	0	0
	12' high	1.22	43.68	lin. ft.	0	0	0	0	0	0
	16' high	1.62	58.24	lin. ft.	0	0	0	0	0	0
Wooden Columns 8" diameter	9' high	3.14	138	each	0	0	0	0	0	0
	10' high	3.5	154	each	0	0	0	0	0	0
	12' high	4.18	184	each	0	0	0	0	0	0
	16' high	5.6	246	each	0	0	0	0	0	0
	17' hi h	5.95	261.8	each	0	0	0	0	0	0
Steel Beams:	W21 x 62	0.127	62	lin. ft.	0	0	0	0	0	0
Steel Plate:	0.5" thick	0.04	19.48	sq ft.	0	0	0	0	0	0
Windows: 8' X 13'	1" plyw'd	8.91	338	each	0	0	0	0	0	0
	1/64" met	0.14	68	each	0	0	0	0	0	0
		9.05	406	each	0	0	0	0	0	0
Total square feet/pounds:					1186.812	32076	35851.71	969547.5	35851.71	969547.5
Total cubic yards:					43.95952	cu. yds.	1327.947	cu. yds.	1327.947	cu. yds.
Total Tons:					16.038	Tons	484.7738	Tons	484.7738	Tons
TOTAL TSCA MATERIAL VOLUME:					3889.851	cubic yards				
TOTAL TSCA MATERIAL MASS:					1993.579	Tons				

1327.947 cu. yds.
484.7738 Tons

43.95952 cu. yds.
16.038 Tons

1327.947 cu. yds.
484.7738 Tons

1327.947 cu. yds.
484.7738 Tons

Table B-3

Aerovox, Inc. Facility

Materials to TSCA Landfill Under Option #2 (Including a Portion of the Concrete Floor at Grade)

Western Section:

Structure	Size	Volume Per Unit [cf]	Mass Per Unit [lb]	Unit	1st Floor		2nd Floor	
					No. of Units	Volume [cf]	Mass [lb]	No. of Units
Base Concrete Wall:	1' thick	3	540	lin. ft.	0	0	0	0
Concrete Floor:	6" thick	0.5	90	sq. ft.	96920	48460	8722800	15000 7500 1350000
Brick Walls:	12" thick	1	112	sq. ft.	0	0	0	0
	16" thick	1.333	150	sq. ft.	0	0	0	0
Wooden Walls/Floor:	4" thick	0.333	9	sq. ft.	3186	1060.938	28674	0 0
	5" thick	0.416	11.25	sq. ft.	0	0	0	56650 23566.4 637312.5
Drywall:	9' high	0.91	36.5	lin. ft.	0	0	0	0
	10' high	1.01	40.5	lin. ft.	0	0	0	0
	12' high	1.22	48.7	lin. ft.	0	0	0	0
Wooden Columns	9' high	3.14	138	each	0	0	0	0
8" diameter	10' high	3.5	154	each	0	0	0	0
	12" high	4.18	184	each	0	0	0	0
	16' high	5.6	246	each	0	0	0	0
Steel Beams:	W21 x 62	0.127	62	lin. ft.	0	0	0	0
Steel Plate	0.5" thick	0.04	19.48	sq. ft.	0	0	0	0
Windows:	1" plyw'd	5.83	221	each	0	0	0	0
6' X 11'	1/64" met	0.09	44.7	each	0	0	0	0
		5.92	265.7	each	0	0	0	0
Total square feet/pounds:					49520.94	8751474	31066.4	1987313
Total cubic yards:					1834.256	cu. yds.	1150.699	cu. yds.
Total Tons:					4375.737	Tons	993.6563	Tons

Table B-3 - cont.

Aerovox, Inc. Facility

Materials to TSCA Landfill Under Option #2 (Including a Portion of the Concrete Floor at Grade)

Eastern Section

Structure	Size	Volume Per Unit [cf]	Mass Per Unit [lb]	Unit	1st Floor			2nd Floor			3rd Floor				
					No. of Units	Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]		
Base Wall:	1' thick	3	540	lin. ft.	0	0	0	0	0	0	0	0	0	0	
Brick Walls:	12" thick	1	112	sq. ft.	0	0	0	0	0	0	0	0	0	0	
	16" thick	1.333	150	sq. ft.	0	0	0	0	0	0	0	0	0	0	
Wooden Walls/Floor:	4" thick	0.333	9	sq. ft.	3564	1186.812	32076	0	0	0	0	0	0	0	
	5" thick	0.416	11.25	sq. ft.	0	0	0	86182	35851.71	969547.5	86182	35851.71	969547.5	86182	35851.71
Drywall:	9' high	0.91	36.5	lin. ft.	0	0	0	0	0	0	0	0	0	0	
	10' high	1.01	40.5	lin. ft.	0	0	0	0	0	0	0	0	0	0	
	12' high	1.22	48.7	lin. ft.	0	0	0	0	0	0	0	0	0	0	
Particle Board Wall:	10' high	1.01	36.4	lin. ft.	0	0	0	0	0	0	0	0	0	0	
	12' high	1.22	43.68	lin. ft.	0	0	0	0	0	0	0	0	0	0	
	16' high	1.62	58.24	lin. ft.	0	0	0	0	0	0	0	0	0	0	
Wooden Columns	9" high	3.14	138	each	0	0	0	0	0	0	0	0	0	0	
	10" high	3.5	154	each	0	0	0	0	0	0	0	0	0	0	
	12" high	4.18	184	each	0	0	0	0	0	0	0	0	0	0	
	16" high	5.6	246	each	0	0	0	0	0	0	0	0	0	0	
	17" high	5.95	261.8	each	0	0	0	0	0	0	0	0	0	0	
Steel Beams:	W21 x 62	0.127	62	lin. ft.	0	0	0	0	0	0	0	0	0	0	
Steel Plate:	0.5" thick	0.04	19.48	s. ft.	0	0	0	0	0	0	0	0	0	0	
Windows:	1" plyw'd	8.91	338	each	0	0	0	0	0	0	0	0	0	0	
	1/64" met	0.14	68	each	0	0	0	0	0	0	0	0	0	0	
		9.05	406	each	0	0	0	0	0	0	0	0	0	0	
Total square feet/pounds:					1186.812	32076		35851.71	969547.5		35851.71	969547.5		35851.71	969547.5
Total cubic yards:					43.95952	cu. yds.		1327.947	cu. yds.		1327.947	cu. yds.		1327.947	cu. yds.
Total Tons:					16.038	Tons		484.7738	Tons		484.7738	Tons		484.7738	Tons

TOTAL TSCA MATERIAL VOLUME: 5684.809 cubic yards

TOTAL TSCA MATERIAL MASS: 6354.979 Tons

Table B-4

Aerovox, Inc. Facility

Materials to TSCA Landfill Under Option #3 (Including Entire Concrete Floor at Grade)

Basic Units: Western Section:

Structure	Size	Volume Per Unit [cf]	Mass Per Unit [lb]	Unit	1st Floor			2nd Floor			
					No. of Units	Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]	
Base Concrete Wall:	1' thick	3	540	lin. ft.	0	0	0	0	0	0	
Concrete Floor:	6" thick	0.5	90	sq. ft.	96920	48460	8722800	15000	7500	1350000	
Brick Walls:	12" thick	1	112	sq. ft.	0	0	0	0	0	0	
	16" thick	1.333	150	sq. ft.	0	0	0	0	0	0	
Wooden Walls/Floor:	4" thick	0.333	9	sq. ft.	3186	1060.938	28674	56650	23566.4	637312.5	
	5" thick	0.416	11.25	sq. ft.	0	0	0	0	0	0	
Drywall:	9' high	0.91	36.5	lin. ft.	0	0	0	0	0	0	
2"X4" stud every 2'	10' high	1.01	40.5	lin. ft.	0	0	0	0	0	0	
	12' high	1.22	48.7	lin. ft.	0	0	0	0	0	0	
Wooden Columns	9' high	3.14	138	each	0	0	0	0	0	0	
8" diameter	10' high	3.5	154	each	0	0	0	0	0	0	
	12" high	4.18	184	each	0	0	0	0	0	0	
	16' high	5.6	246	each	0	0	0	0	0	0	
Steel Beams:	W21 x 62	0.127	62	lin. ft.	0	0	0	0	0	0	
Steel Plate	0.5" thick	0.04	19.48	sq. ft.	0	0	0	0	0	0	
Windows:	1" plyw'd	5.83	221	each	0	0	0	0	0	0	
6' X 11'	1/64" met	0.09	44.7	each	0	0	0	0	0	0	
		5.92	265.7	each	0	0	0	0	0	0	
Total square feet/pounds:					49520.94	8751474		31066.4	1987313		
Total cubic yards:					1834.256	cu. yds.		1150.699	cu. yds.		
Total Tons:					4375.737	Tons		993.6563	Tons		

Table B-4 - cont.

Aerovox, Inc. Facility

Materials to TSCA Landfill Under Option #3 (including Entire Concrete Floor at Grade)

Eastern Section

Structure	Size	Volume		Unit	1st Floor		2nd Floor		3rd Floor		
		[cf]	[lb]		No. of Units	Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]	
Base Wall:	1" thick	3	540	lin. ft.	0	0	0	0	0	0	
Concrete Floor:	6" thick	0.5	90	sq. ft.	85214	42607	7669260	0	0	0	
Brick Walls:	12" thick	1	112	sq. ft.	0	0	0	0	0	0	
	16" thick	1.333	150	sq. ft.	0	0	0	0	0	0	
Wooden Walls/Floor	4" thick	0.333	9	sq. ft.	3564	1186.812	32076	0	0	0	
	5" thick	0.416	11.25	sq. ft.	0	0	0	86182	35851.71	969547.5	
Drywall:	9' high	0.91	36.5	lin. ft.	0	0	0	0	0	0	
	2"X4" stud every 2 ft	1.01	40.5	lin. ft.	0	0	0	0	0	0	
	12' hi h	1.22	48.7	lin. ft.	0	0	0	0	0	0	
Particle Board Wall:	10' high	1.01	36.4	lin. ft.	0	0	0	0	0	0	
	0.5" thick board	1.22	43.68	lin. ft.	0	0	0	0	0	0	
	2"X4" stud every 2'	1.62	58.24	lin. ft.	0	0	0	0	0	0	
Wooden Columns	9' high	3.14	138	each	0	0	0	0	0	0	
	10' high	3.5	154	each	0	0	0	0	0	0	
	12' high	4.18	184	each	0	0	0	0	0	0	
	16' high	5.6	246	each	0	0	0	0	0	0	
	17' high	5.95	261.8	each	0	0	0	0	0	0	
Steel Beams:	W21 x 62	0.127	62	lin. ft.	0	0	0	0	0	0	
Steel Plate:	0.5" thick	0.04	19.48	sq. ft.	0	0	0	0	0	0	
Windows:	1" plywd	8.91	338	each	0	0	0	0	0	0	
	1/64" met	0.14	68	each	0	0	0	0	0	0	
		9.05	406	each	0	0	0	0	0	0	
Total square feet/pounds:					43793.81	7701336		35851.71	969547.5	35851.71	969547.5
Total cubic yards:					1622.123	cu. yds.		1327.947	cu. yds.	1327.947	cu. yds.
Total Tons:					3850.668	Tons		484.7738	Tons	484.7738	Tons

TOTAL TSCA MATERIAL VOLUME: 7262.973 cubic yards
 TOTAL TSCA MATERIAL MASS: 10189.61 Tons

Table B-5

Aerovox, Inc. Facility

Materials to Non-TSCA Landfill Under Option #1

Structure	Size	Volume Per Unit [cf]	Mass Per Unit [lb]	Unit	Western Section:			2nd Floor		
					No. of Units	Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]
Base Concrete Wall:	1' thick	3	540	lin. ft.	1432	4296	773280		0	0
Concrete Floor:	6" thick	0.5	90	sq. ft.		0	0		0	0
Brick Walls:	12" thick	1	112	sq. ft.	5064	5064	567168	3006	3006	336672
	16" thick	1.333	150	sq. ft.	13239	17647.59	1985850	4704	6270.432	705600
Wooden Walls/Floor	4" thick	0.333	9	sq. ft.	2800	932.4	25200		0	0
	5" thick	0.416	11.25	sq. ft.		0	0	25000	10400	281250
Drywall:	9' high	0.91	36.5	lin. ft.	1100	1001	40150		0	0
	2"X4" stud every 2'	1.01	40.5	lin. ft.	180	181.8	7290	2500	2525	101250
	12" high	1.22	48.7	lin. ft.	550	671	26785		0	0
Wooden Columns	9' high	3.14	138	each	176	552.64	24288		0	0
	10' high	3.5	154	each	25	87.5	3850		0	0
	12" high	4.18	184	each	108	451.44	19872		0	0
	16' hi h	5.6	246	each		0	0	84	470.4	20664
Steel Beams:	W21 x 62	0.127	62	lin. ft.		0	0		0	0
Steel Plate	0.5" thick	0.04	19.48	sq. ft.		0	0		0	0
Windows:	1" plyw'd	5.83	221	each		0	0	26	151.58	5746
	1/64" met	0.09	44.7	each		0	0		0	0
		5.92	265.7	each		0	0		0	0
Total square feet/pounds:						30885.37	3473733		22823.41	1451182
Total cubic yards:						1143.994	cu. yds.		845.3792	cu. yds.
Total Tons:						1736.867	Tons		725.591	Tons
Roof - Western Section:						1875	cubic yards			
						658	Tons			

Table B-5 - cont.

Aerovox, Inc. Facility

Materials to Non-TSCA Landfill Under Option #1

Eastern Section

Basic Units:

1st Floor

2nd Floor

3rd Floor

Structure	Size	Volume		Unit	1st Floor			2nd Floor			3rd Floor			
		[cf]	[lb]		No. of Units	Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]	
Base Wall:	1' thick	3	540	lin. ft.	1425	4275	769500	0	0	0	0	0	0	0
Brick Walls:	12" thick	1	112	sq. ft.	2246	2246	251552	2325	2325	260400	3525	3525	394800	
	16" thick	1.333	150	sq. ft.	4194	5590.602	629100	7650	10197.45	1147500	8116	10818.63	1217400	
Wooden Walls/Floor	4" thick	0.333	9	sq. ft.										
	5" thick	0.416	11.25	s. pft.										
Drywall:	9' high	0.91	36.5	lin. ft.										
	2"X4" stud every 2 ft	1.01	40.5	lin. ft.										
	12' hi h	1.22	48.7	q lin. ft.										
Particle Board Wall:	10' high	1.01	36.4	lin. ft.										
	12' high	1.22	43.68	lin. ft.	3100	3782	135408	2365	2388.65	86086	2320	2343.2	84448	
	2"X4" stud every 2'	1.62	58.24	lin. ft.										
Wooden Columns	9' high	3.14	138	each										
	10' high	3.5	154	each										
	12' high	4.18	184	each	220	919.6	40480							
	16' high	5.6	246	each				220	1232	54120				
	17' high	5.95	261.8	each							220	1309	57596	
Steel Beams:	W21 x 62	0.127	62	lin. ft.										
Steel Plate:	0.5" thick	0.04	19.48	s. ft.										
Windows:	1" plyw'd	8.91	338	each	56	498.96	18928	119	1060.29	40222	119	1060.29	40222	
	1/64" met	0.14	68	each										
		9.05	406	each										
Total square feet/pounds:						17312.16	1844968		17203.39	1588328		19056.12	1794466	
Total cubic yards:						641.2425	cu. yds.		637.2136	cu. yds.		705.8386	cu. yds.	
Total Tons:						922.484	Tons		794.164	Tons		897.233	Tons	

Roof - Eastern Section: 1474 cubic yards
517 Tons

TOTAL NON-TSCA MATERIAL VOLUME: 7322.668 cubic yards
TOTAL NON-TSCA MATERIAL MASS: 6251.339 Tons

Table B-6

Aerovox, Inc. Facility

Materials to Non-TSCA Landfill Under Options #2 and #3

Structure	Size	Volume Per Unit [cf]	Mass Per Unit [lb]	Unit	1st Floor			2nd Floor		
					No. of Units	Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]
Base Concrete Wall:	1' thick	3	540	lin. ft.	0	0	0	0	0	0
Concrete Floor:	6" thick	0.5	90	sq. ft.	0	0	0	0	0	0
Brick Walls:	12" thick	1	112	sq. ft.	0	0	0	0	0	0
	16" thick	1.333	150	sq. ft.	0	0	0	0	0	0
Wooden Walls/Floor:	4" thick	0.333	9	sq. ft.	2800	932.4	25200	25000	10400	281250
	5" thick	0.416	11.25	sq. ft.	0	0	0	0	0	0
Drywall:	9' high	0.91	36.5	lin. ft.	1100	1001	40150	0	0	0
	2"X4" stud every 2'	1.01	40.5	lin. ft.	180	181.8	7290	2500	2525	101250
	12' hi h	1.22	48.7	lin. ft.	550	671	26785	0	0	0
Wooden Columns:	9' high	3.14	138	each	176	552.64	24288	0	0	0
	8" diameter	3.5	154	each	25	87.5	3850	0	0	0
	12" high	4.18	184	each	108	451.44	19872	0	0	0
	16' hi h	5.6	246	each	0	0	0	84	470.4	20664
Steel Beams:	W21 x 62	0.127	62	lin. ft.	0	0	0	0	0	0
Steel Plate:	0.5" thick	0.04	19.48	sq. ft.	0	0	0	0	0	0
Windows:	1" plyw'd	5.83	221	each	0	0	0	26	151.58	5746
	6' X 11'	1/64" met	44.7	each	0	0	0	0	0	0
		5.92	265.7	each	0	0	0	0	0	0
Total square feet/pounds:					3877.78	147435		13546.98	408910	
Total cubic yards:					143.633	cu. yds.		501.7801	cu. yds.	
Total Tons:					73.7175	Tons		204.455	Tons	

Roof - Western Section: 1875 cubic yards
658 Tons

Table B-6 - cont.

Aerovox, Inc. Facility

Materials to Non-TSCA Landfill Under Options #2 and #3

Eastern Section

Structure	Size	Volume Per Unit [cf]	Mass Per Unit [lb]	Unit	1st Floor			2nd Floor			3rd Floor			
					No. of Units	Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]	
Base Wall:	1' thick	3	540	lin. ft.	0	0	0	0	0	0	0	0	0	0
Brick Walls:	12" thick	1	112	sq. ft.	0	0	0	0	0	0	0	0	0	0
	16" thick	1,333	150	s. ft.	0	0	0	0	0	0	0	0	0	0
Wooden Walls/Floor	4" thick	0.333	9	sq. ft.	0	0	0	0	0	0	0	0	0	0
	5" thick	0.416	11.25	sq. ft.	0	0	0	0	0	0	0	0	0	0
Drywall:	9' high	0.91	36.5	lin. ft.	0	0	0	0	0	0	0	0	0	0
	10' high	1.01	40.5	lin. ft.	0	0	0	0	0	0	0	0	0	0
	12' high	1.22	48.7	lin. ft.	0	0	0	0	0	0	0	0	0	0
Particle Board Wall:	10' high	1.01	36.4	lin. ft.	0	0	0	0	0	0	0	0	0	0
	12' high	1.22	43.68	lin. ft.	3100	3782	135408	2365	2388.65	86086	2320	2343.2	84448	
	16' high	1.62	58.24	lin. ft.	0	0	0	0	0	0	0	0	0	
Wooden Columns 8" diameter	9' high	3.14	138	each.	0	0	0	0	0	0	0	0	0	0
	10' high	3.5	154	each	0	0	0	0	0	0	0	0	0	0
	12' high	4.18	184	each	220	919.6	40480	220	1232	54120	220	1309	57596	
	16' high	5.6	246	each	0	0	0	0	0	0	0	0	0	
	17' high	5.95	261.8	each	0	0	0	0	0	0	0	0	0	
Steel Beams:	W21 x 62	0.127	62	lin. ft.	0	0	0	0	0	0	0	0	0	0
Steel Plate:	0.5" thick	0.04	19.48	s. ft.	0	0	0	0	0	0	0	0	0	0
Windows: 8' X 13'	1" plyw'd	8.91	338	each	56	498.96	18928	119	1060.29	40222	119	1060.29	40222	
	1/64" met	0.14	68	each	0	0	0	0	0	0	0	0	0	
		9.05	406	each	0	0	0	0	0	0	0	0	0	
Total square feet/pounds:					5200.56	194816		4680.94	180428		4712.49	182266		
Total cubic yards:					192.6287	cu. yds.		173.382	cu. yds.		174.5506	cu. yds.		
Total Tons:					97.408	Tons		90.214	Tons		91.133	Tons		
Roof - Eastern Section:					1474	cubic yards		517	Tons					
TOTAL NON-TSCA MATERIAL VOLUME:					4534.975	cubic yards								
TOTAL NON-TSCA MATERIAL MASS:					1731.928	Tons								

Table B-7

Aerovox, Inc. Facility

Non-TSCA Materials to be used as Backfill Under Options #2 and #3

Structure	Size	Volume Per Unit [cf]	Mass Per Unit [lb]	Unit	1st Floor			2nd Floor		
					No. of Units	Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]
Base Concrete Wall:	1' thick	3	540	lin. ft.	1432	4296	773280	0	0	0
Concrete Floor:	6" thick	0.5	90	sq. ft.	0	0	0	0	0	0
Brick Walls:	12" thick	1	112	sq. ft.	5064	5064	567168	3006	3006	336672
	16" thick	1.333	150	sq. ft.	13239	17647.59	1985850	4704	6270.432	705600
Wooden Walls/Floor:	4" thick	0.333	9	sq. ft.	0	0	0	0	0	0
	5" thick	0.416	11.25	sq. ft.	0	0	0	0	0	0
Drywall:	9' high	0.91	36.5	lin. ft.	0	0	0	0	0	0
	10' high	1.01	40.5	lin. ft.	0	0	0	0	0	0
	12' ht h	1.22	48.7	lin. ft.	0	0	0	0	0	0
Wooden Columns	9' high	3.14	138	each	0	0	0	0	0	0
	10' high	3.5	154	each	0	0	0	0	0	0
	12" high	4.18	184	each	0	0	0	0	0	0
	16' high	5.6	246	each	0	0	0	0	0	0
Steel Beams:	W21 x 62	0.127	62	lin. ft.	0	0	0	0	0	0
Steel Plate	0.5" thick	0.04	19.48	s. ft.	0	0	0	0	0	0
Windows:	1" plyw'd	5.83	221	each	0	0	0	0	0	0
	1/64" met	0.09	44.7	each	0	0	0	0	0	0
		5.92	265.7	each	0	0	0	0	0	0
Total square feet/pounds:					27007.59	3326298	9276.432	1042272		
Total cubic yards:					1000.361	cu. yds.	343.599	cu. yds.		
Total Tons:					1663.149	Tons	521.136	Tons		

Roof - Western Section: 0 cubic yards
0 Tons

Table B-7 - cont.

Aerovox, Inc. Facility

Non-TSCA Materials to be used as Backfill Under Options #2 and #3

Eastern Section

Basic Units:

1st Floor

2nd Floor

3rd Floor

Structure	Size	Volume		Unit	No. of Units	Mass		No. of Units	Mass		No. of Units	Mass	
		[cf]	[lb]			[cf]	[lb]		[cf]	[lb]		[cf]	[lb]
Base Wall:	1' thick	3	540	lin. ft.	1425	4275	769500		0	0		0	0
Brick Walls:	12" thick	1	112	sq. ft.	2246	2246	251552	2325	2325	260400	3525	3525	394800
	16" thick	1.333	150	sq. ft.	4194	5590.602	629100	7650	10197.45	1147500	8116	10818.63	1217400
Wooden Walls/Floor	4" thick	0.333	9	sq. ft.		0	0		0	0		0	0
	5" thick	0.416	11.25	sq. ft.		0	0		0	0		0	0
Drywall:	9' high	0.91	36.5	lin. ft.		0	0		0	0		0	0
	10' high	1.01	40.5	lin. ft.		0	0		0	0		0	0
	12' high	1.22	48.7	lin. ft.		0	0		0	0		0	0
Particle Beard Wall:	10' high	1.01	36.4	lin. ft.		0	0		0	0		0	0
	12' high	1.22	43.68	lin. ft.		0	0		0	0		0	0
	16' high	1.62	58.24	lin. ft.		0	0		0	0		0	0
Wooden Columns	9' high	3.14	138	each		0	0		0	0		0	0
	10' high	3.5	154	each		0	0		0	0		0	0
	12' high	4.18	184	each		0	0		0	0		0	0
	16' high	5.6	246	each		0	0		0	0		0	0
	17' high	5.95	261.8	each		0	0		0	0		0	0
Steel Beams:	W21 x 62	0.127	62	lin. ft.		0	0		0	0		0	0
Steel Plate:	0.5" thick	0.04	19.48	sq. ft.		0	0		0	0		0	0
Windows:	1" plyw'd	8.91	338	each		0	0		0	0		0	0
	1/64" met	0.14	68	each		0	0		0	0		0	0
		9.05	406	each		0	0		0	0		0	0
Total square feet/pounds:						12111.6	1650152		12522.45	1407900		14343.63	1612200
Total cubic yards:						448.6137	cu. yds.		463.8315	cu. yds.		531.288	cu. yds.
Total Tons:						825.076	Tons		703.95	Tons		806.1	Tons

Roof - Eastern Section: 0 cubic yards
0 Tons

TOTAL NON-TSCA BACKFILL MATERIAL VOLU 2787.693 cubic yards
TOTAL NON-TSCA BACKFILL MATERIAL MASS: 4519.411 Tons

Table B-8

Aerovox, Inc. Facility

Materials to Steel Smelting Facility

Western Section:

Basic Units:

Structure	Size	Volume Per Unit [cf]	Mass Per Unit [lb]	Unit	1st Floor			2nd Floor		
					No. of Units	Volume [cf]	Mass [lb]	No. of Units	Volume [cf]	Mass [lb]
Base Concrete Wall:	1' thick	3	540	lin. ft.	0	0	0	0	0	0
Concrete Floor:	6" thick	0.5	90	sq. ft.	0	0	0	0	0	0
Brick Walls:	12" thick	1	112	sq. ft.	0	0	0	0	0	0
	16" thick	1.333	150	sq. ft.	0	0	0	0	0	0
Wooden Walls/Floor:	4" thick	0.333	9	sq. ft.	0	0	0	0	0	0
	5" thick	0.416	11.25	sq. ft.	0	0	0	0	0	0
Drywall:	9' high	0.91	36.5	lin. ft.	0	0	0	0	0	0
	10' high	1.01	40.5	lin. ft.	0	0	0	0	0	0
	12' high	1.22	48.7	lin. ft.	0	0	0	0	0	0
Wooden Columns 8" diameter	9' high	3.14	138	each	0	0	0	0	0	0
	10' high	3.5	154	each	0	0	0	0	0	0
	12' high	4.18	184	each	0	0	0	0	0	0
	16' high	5.6	246	each	0	0	0	0	0	0
Steel Beams:	W21 x 62	0.127	62	lin. ft.	9320	1183.64	577840	4583	582.041	284146
Steel Plate	0.5" thick	0.04	19.48	sq. ft.	0	0	0	3925	157	76459
Windows: 6' X 11'	1" plyw'd	5.83	221	each	0	0	0	26	2.34	1162.2
	1/64" met	0.09	44.7	each	0	0	0	0	0	0
Total square feet/pounds:					1183.64	577840	741.381	361767.2		
Total cubic yards:					43.84203	cu. yds.		27.46075	cu. yds.	
Total Tons:					288.92	Tons		160.8636	Tons	

Table B-8 - cont.

Aerovox, Inc. Facility

Materials to Steel Smelting Facility

Eastern Section

Basic Units:

3rd Floor


2nd Floor

1st Floor

Structure	Size	Volume		Unit	No. of Units	1st Floor		2nd Floor		3rd Floor			
		[cf]	[lb]			Volume [cf]	Mass [lb]	Volume [cf]	Mass [lb]	Volume [cf]	Mass [lb]		
Base Wall:	1' thick	3	540	lin. ft.		0	0	0	0	0	0		
Brick Walls:	12" thick	1	112	sq. ft.		0	0	0	0	0	0		
	16" thick	1.333	150	sq. ft.		0	0	0	0	0	0		
Wooden Walls/Floor:	4" thick	0.333	9	sq. ft.		0	0	0	0	0	0		
	5" thick	0.416	11.25	sq. ft.		0	0	0	0	0	0		
Drywall:	9' high	0.91	36.5	lin. ft.		0	0	0	0	0	0		
	10' high	1.01	40.5	lin. ft.		0	0	0	0	0	0		
	12' high	1.22	48.7	lin. ft.		0	0	0	0	0	0		
Particle Board Wall:	10' high	1.01	36.4	lin. ft.		0	0	0	0	0	0		
	12' high	1.22	43.68	lin. ft.		0	0	0	0	0	0		
	16' high	1.62	58.24	lin. ft.		0	0	0	0	0	0		
Wooden Columns 8" diameter	9' high	3.14	138	each		0	0	0	0	0	0		
	10' high	3.5	154	each		0	0	0	0	0	0		
	12' high	4.18	184	each		0	0	0	0	0	0		
	16' high	5.6	246	each		0	0	0	0	0	0		
	17' high	5.95	261.8	each		0	0	0	0	0	0		
Steel Beams:	W21 x 62	0.127	62	lin. ft.	7535	956.945	467170	7535	956.945	467170	7535	956.945	467170
Steel Plate:	0.5" thick	0.04	19.48	sq. ft.		0	0	4728	189.12	92101.44		0	0
Windows: 8' X 13'	1" plyw'd	8.91	338	each		0	0		0	0		0	0
	1/64" met	0.14	68	each	56	7.84	3808	119	16.66	8092	119	16.66	8092
		9.05	406	each		0	0		0	0		0	0
Total square feet/pounds:						964.785	470978		1162.725	567363.4		973.605	475262
Total cubic yards:						35.73564	cu. yds.		43.06733	cu. yds.		36.06233	cu. yds.
Total Tons:						235.489	Tons		283.8817	Tons		237.631	Tons
TOTAL STEEL VOLUME:						186.1681	cubic yards						
TOTAL STEEL MASS:						1226.605	Tons						

CALCS. BY _____; DATE _____ CHECKED BY JCB; DATE 3/26/98

Area and Volume Calculations for Concrete Floor Slab:



Area Calculations:

$A_1 = (220')(325') = 71,500 \text{ sf}$
 $A_2 = (622')(137') = 85,214 \text{ sf}$
 $A_{2A} = (285')(137') = 39,045 \text{ sf}$
 $A_{2B} = (337')(137') = 46,169 \text{ sf}$
 $A_3 = (103')(46') = 4,738 \text{ sf}$

Volume of Concrete Floor Below Grade:

Assumptions: Areas A_1, A_3, A_4, A_5 below Grade 6'
 Area A_{2A} below Grade 3.5'
 Area A_{2B} below Grade 1.5'

$A_4 = (107')(158') = 16,906 \text{ sf}$
 $A_5 = (20 \times 88) + (36)(56) = 3,776 \text{ sf}$

$V_1 = (71,500 \text{ sf})(6') = 429,000 \text{ cf} = 15,888.9 \text{ cy}$

$A_{TOTAL} = 182,134 \text{ sf}$

$V_{2A} = (39,045 \text{ sf})(3.5') = 136,657.5 \text{ cf} = 5,061.4 \text{ cy}$

(excluding A_{2A} and A_{2B}) = 20,237 sf ✓

$V_{2B} = (46,169 \text{ sf})(1.5') = 69,253.5 \text{ cf} = 2,564.9 \text{ cy}$

$V_2 = V_{2A} + V_{2B} = 136,657.5 \text{ cf} + 69,253.5 \text{ cf} = 205,911 \text{ cf} = 7,626.3 \text{ cy}$

$V_3 = (4,738 \text{ sf})(6') = 28,428 \text{ cf} = 1,052.9 \text{ cy}$

$V_4 = (16,906 \text{ sf})(6') = 101,436 \text{ cf} = 3,756.9 \text{ cy}$

$V_5 = (3,776 \text{ sf})(6') = 22,656 \text{ cf} = 839.1 \text{ cy}$

$V_{TOTAL} = 787,431 \text{ cf}$

= 29,164.1 cy ✓

SUBJECT AeroVox, Inc. Facility - Building Demolition Alternative	PROJ. NO. 03955.004	BY CEG	DATE 3/25/98	SHEET 2/4
---	------------------------	-----------	-----------------	--------------

ALCS. BY _____; DATE _____ CHECKED BY JCB; DATE 3/26/98

Amount of Backfill Required:

Thickness of Cap to be Installed: 6" sand + 6" gravel + 4" asphalt = 1'4"

Assumption:

- Building Area will be backfilled up to 1 foot below Grade with the remaining volume to be filled with cap material.
- Concrete Floor Slab Thickness is 6 inches

Option #1:

• Volume of Demolition Materials to be Used as Backfill Under Options #2 and #3 is 2787.7 CY

Volume of Backfill Required

$$V_{OPT\#1} = (71,500)(5') + (39,045)(2.5') + (46,169)(0.5') + (4,738)(5') + (16,906)(5') + (3,776)(5') = 605,297 \text{ cf} = 22,448.4 \text{ CY} \checkmark$$

Option #2:

Area of Concrete to be Removed

$$A_{CONCRETE\#2} = A_1 + A_3 + A_4 + A_5 = (71,500) + (4,738) + (16,906) + (3,776) = 96,920 \text{ sf} \checkmark$$

Volume of Fill Required

$$V_{OPT\#2} = (71,500)(5+0.5) + (4,738)(5+0.5) + (16,906)(5+0.5) + (3,776)(5+0.5) + (39,045)(2.5) + (46,169)(0.5) = 653,757 \text{ CF} = 24,213.2 \text{ CY}$$

Option #3:

Area of Concrete to be Removed

$$V_{OPT\#2} = 21,425.5 \text{ CY}$$

$$A_{CONCRETE\#3} = A_1 + A_{2A} + A_{2B} + A_3 + A_4 + A_5 = A_{TOTAL} = 182,134 \text{ sf}$$

Volume of Fill Required

$$V_{OPT\#3} = (71,500)(5+0.5) + (39,045)(2.5+0.5) + (46,169)(0.5+0.5) + (4,738)(5+0.5) + (16,906)(5+0.5) + (3,776)(5+0.5) = 696,364 \text{ CF} = 25,791.3 \text{ CY}$$

$$V_{OPT\#3} = 23,003.6 \text{ CY} \checkmark$$

SUBJECT	PROJ. NO.	BY	DATE	SHEET
Aerovox, Inc. Facility - Building Demolition Alternative	63855,004	CEG	3/25/18	3/4

CALCS. BY _____; DATE _____

CHECKED BY JCB; DATE 3/26/18Volume of Materials Required for Asphalt Cap:Volume of 2" Sand Fill Layer:

$$\text{Area of Cap} = 182,134 \text{ sf}$$

$$V_{SF} = (182,134 \text{ sf}) \left(\frac{2}{12}'\right) = 30,356 \text{ cf} = 1,124.3 \text{ cy}$$

Volume of 6" Crusher Run Layer:

$$\text{Area of Cap} = 182,134 \text{ sf}$$

$$V_{CR} = (182,134 \text{ sf}) (0.5') = 91,067 \text{ cf} = 3,372.9 \text{ cy}$$

Volume of 4" Asphalt:

$$\text{Area of Cap} = 182,134 \text{ sf}$$

$$V_{AS} = (182,134 \text{ sf}) (0.33') = 60,104 \text{ cf} = 2,226.1 \text{ cy}$$

SUBJECT	PROJ. NO.	BY	DATE	SHEET
Aerovox, Inc. Facility - Building Demolition Alternative	03855.009	CEG	3/25/98	4/4

CALCS. BY _____; DATE _____ CHECKED BY JCB; DATE 3/26/98

Cost for Asphalt Cap:

Area of Cap = 20,237 SY = 182,133 sf

- 40 ml PVC Liner @ \$0.34/sf x 182,133 sf = \$61,925.22
- Geogrid, Nylon Geomatrix / NC-coated Polyester \$1.40/sf x 182,133 sf = \$254,986.20
- 2" Sand Layer @ \$13.00/cy x 1,124 cy = \$14,612.00
- 6" Subgrade Layer (Crusher Run) \$18.97/cy x 3,373 cy = \$62,299.31
- 2 1/2" Bituminous concrete base course @ \$4.50/sy x 20,237 sy = 91,066.50
- 1 1/2" Bituminous concrete wearing surface @ \$3.30/sy x 20,237 sy = 66,782.10

551,671.33

÷ 20,237 SY

\$ 27.26